

**SURVEY & REMONUMENTATION**

FEB 18 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Approved By Delta County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On Jan. 20, 1994

*Walter C. Thorne*  
 Acting Chairman

For corners in

DELTA

(County)

Located In:

Corner Code ##

- |                                    |   |             |   |             |                      |
|------------------------------------|---|-------------|---|-------------|----------------------|
| 1. Public Land Survey              | T | <u>40 N</u> | R | <u>22 W</u> | <u>E-5 &amp; R-7</u> |
|                                    | T | _____       | R | _____       | _____                |
|                                    | T | _____       | R | _____       | _____                |
|                                    | T | _____       | R | _____       | _____                |
| 2. Property Controlling in Section | S | _____       | T | _____       | _____                |
|                                    | S | _____       | T | _____       | _____                |
| 3. Miscellaneous Property in Sec.  | S | _____       | T | _____       | _____                |
|                                    | S | _____       | T | _____       | _____                |

Recorded January 21, 1994

9:00 a.m. in hour 7 Page 355

*Walter C. Thorne* Reg. of Deeds,  
 Delta County, Michigan

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_  
[B-5] N1/4 COR SEC 18 [E-7] NW COR SEC 21

I, M.P. DAVIS, in a field survey on NOVEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

B-5 [N1/4 COR SEC 18] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (TAMERAC 7°-N29°E-25 LINKS) (TAMERAC 10°-S37°W-37 LINKS) C.E. BROTHERTON - 1885 - STAKE IN PLACE - NO NEW WIT'S NOTED  
 M.S. McNABB - 1932 - NO EVIDENCE OF COR MON FOUND - ESTABLISHED BETWEEN COR'S - SET IP - CEDAR STUMP 14°-S30°E-20.5'

E-7 [NW COR SEC 21] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (W.PINE 22°-N30°W-94 LINKS) (NORWAY PINE 18°-S60°E-96 LINKS) GEORGE NAULT-RLS 6521 (FOR M.D.O.T.) 1971 - FOUND IRON PIN ON PLACE (J.PINE 12°-N70°E-32.19') (CONC MON EAST 30.0') (OAK 16°-S65°E-18.36') (JACK PINE 5°-S40°E-20.81') (PP-WEST-19.30')

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

B-5 [N1/4 COR SEC 18] FOUND McNABB'S 1932 IP - ID FROM HIS CEDAR STUMP BT - IRON MARKS STILL PLAIN ACCEPTED EXISTING AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL COR

E-7 [NW COR SEC 21] FOUND IRON PIN AS DESCRIBED IN M.D.O.T. RECORDS - ACCEPTED EXISTING MON AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

B-5 REPLACED EXISTING MONUMENT W/A BERNTSEN A1NB30 ALUMN MON WITH CAP STAMPED TO ID THE COR POSITION  

CEDAR 7"	SURVEY MONUMENT SIGN POS?	CEDAR 5"	CEDAR 7"
N46°W	N45°E	S13°E	S68°W
19.70'	2.59' (TO FACE)	16.04'	20.77'

E-7 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON BOY  

CONC MON	NW COR CONC TELE PAD	OAK 13"
WEST	N72°E	S40°E
33.0'	28.12'	53.92'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis

Date 11/15/93

Surveyor's Michigan License No. 16926