

**SURVEY & REMONUMENTATION**

FEB 18 1994

COMMISSION

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On Jan 20, 1994

*Robert R. Schindler*  
Acting Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code ##

1. Public Land Survey	T <u>40 N</u> R <u>22 W</u>	<u>F-3</u> E-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Recorded January 21, 1994

at 10:00 o'clock A.M. in Liber 7 Page 347

*William C. Thron* Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_  
[F-3] N1/4 COR SEC 9 [E-5] NW COR OF SEC 16

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on NOVEMBER, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the cornerpoints mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

F-3 [N1/4 COR SEC 9] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (HEMLOCK 20"-WEST-31 LINKS) (W.PINE 12"-S70°E-53 LINKS)  
M.S. MCNAEB - 1944 - ESTABLISHED COR POSITION IN C.L. OF N-S COUNTY ROAD WHERE RECORDS SAID COR STOOD PRIOR TO RD CONSTR DROVE  
IRON STAKE - FENCE POSTS S35°W-55.8' & S65°E-39.6'

E-5 [NW COR SEC 16] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (NORWAY PINE 26"-N26°E-62 LINKS) (BLACK OAK 11"-S45°W-56 LINKS)  
M.S. MCNAEB - 1944 - COR IN PLACE - NO NEW WIT'S NOTED OR DESCRIPTION OF MON FOUND GIVEN IN HIS NOTES

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F-3 [N1/4 COR SEC 9] NO EVIDENCE OF MCNAEB'S IRON STAKE FOUND - RESET CORNER POSITION AT MCNAEB'S DISTANCE WEST OF THE NE COR OF SEC 9 & IN LINE WITH ANCIENT FENCE LINE TO THE WEST ACCEPTED THIS POSITION AS A CAREFUL & FAITHEFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

E-5 [NW COR SEC 16] FOUND AIEL SHAFT IN PLACE - ID CORNER POSITION FROM PLAT OF MARBLE HIGHLANDS AS RECORDED IN LIBER "C" OF PLATS PAGE 38. ACCEPTED AS BEING A CAREFUL & FAITHFULL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

F-3 SET, INSIDE A MON BOX, A 5/8" X 18" REBAR W/A 3-1/4' ALUMN CAP STAMPED TO ID THE CORNER POSITION  
W. PINE 7" 2" I.P. SURVEY MONUMENT SIGN POST  
N37°E EAST WEST  
58.45' 36.88' 9.65' (TO FACE)

E-5 SET, OVER EXISTING MON, A BERNTSEN A1NB30 ALUMN MON W/A CAP STAMPED TO ID THE CORNER POSITION  
ST. SIGN POST POWER POLE POWER POLE SURVEY MONUMENT SIGN POST  
N24°W S21°W S34°W WEST  
42.80' 77.25' 33.25' (TO FACE) 10.57' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis

Date 11/15/93

Surveyor's Michigan License No. 16926

