

FEB 18 1994

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Jan. 20, 1994  
Walter C. Thomas  
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA  
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 40 NR 23 W B-5 B-9  
T     R      
T     R      
T     R
- 2. Property Controlling S     T    R      
in Section S     T    R
- 3. Miscellaneous S     T    R      
Property in Sec. S     T    R

Recorded January 21, 1994  
9:00 o'clock a.m. in Lib. 7 Page 370  
Walter C. Thomas Reg. of Deeds  
Delta County, Michigan  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_  
B-5 [N1/4 COR SEC 18] B-9 [N1/4 COR SEC 30]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on JULY, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 B-5 [N1/4 COR SEC 18] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (BURNT TAMERAC 8"-WEST-50 LINKS) (SPRUCE 8"-S59°E-58 LINKS)  
 M.S. McNABB - 1913 - NO ORIGINALS FOUND - ESTABLISHED PROPORTIONATE DISTANCE BETWEEN CORNERS SET STAKE SCRIBED '1/4'  
 BT STAKES NE & SW 33'  
 M.S. McNABB - 1936 - ID STAKE FROM PREVIOUS SURVEY - SET IRON PIPE (BT STAKE NORTH 25')  
  
 B-9 [N1/4 COR SEC 30] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (MAPLE-S29°E-5 LINKS) (BEECH-N43°E-17 LINKS)  
 M.S. McNABB - 1921 - NO ORIGINALS FOUND - ESTABLISHED PROPORTIONATE DISTANCE BETWEEN CORNERS SET IRON BOLT (STUMP 8"-EAST-24')  
 (FENCE POST- S15°E-5') 1924 SET BT STAKES NW 40' & SE 33'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 B-5 [N1/4 COR SEC 18] FOUND IN PLACE McNABB'S IRON PIPE 24" BELOW COUNTY ROAD SURFACE, ID CORNER POSITION FROM EXISTING OCCUPATION & COMPARISON OF McNABB'S MEASUREMENTS TO ADJOINING CORNERS ACCEPTED THIS MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.  
  
 B-9 [N1/4 COR SEC 30] NO EVIDENCE OF McNABB'S IRON BOLT FOUND, RESTORED CORNER POSITION BY RETRACEMENT OF McNABB'S SURVEY OF THE LINE COMMON TO SEC'S 19/30.  
 ACCEPTED THIS POSITION AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 B-5 SET, OVER EXISTING MON, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID COR POSITION, RAISED TO RD SURFACE W/A MON BOX  
 TAMARACK 4" TAMARACK 8" SPRUCE 9" SURVEY SIGN MONUMENT SIGN POST  
 N65°E S37°W S40°E NORTH  
 83.78' 47.55' 99.46' 15.89' (TO FACE)  
  
 B-9 SET, 6" BELOW ROAD SURFACE, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION  
 DRILL HOLE IN FIELD STONE DRILL HOLE IN FIELD STONE WHITE BIRCH 6" SURVEY MONUMENT SIGN POST  
 N48°E S67°W S81°E SOUTH  
 41.22' 67.40' 150.70' 25.0' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 12/29/93  
Surveyor's Michigan License No. 16926