

# SURVEY & REMONUMENTATION

AUG 20 1996

## COMMISSION

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On February 30, 1993

*Robert Schmeiding*  
acting Chairman

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code #

1. Public Land Survey

T 39 N R 23 W

B-7 & C-1

T \_\_\_\_\_ R \_\_\_\_\_

T 40 N R 23 W

C-13

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

DELTA COUNTY

LIBER 7 PAGE 341

93 DEC -2 AM 9:00

*Walter C. Thoren*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

B-7 [1/4 COR COMMON TO SEC'S 18/19]

C-1 [NW COR SEC 5]

*same as T40N, R23W C-13*

I, M.P. DAVIS

in a field survey on MAY 1993

, 19 93

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-7 [1/4 COR COMMON TO SEC'S 18/19] WOOD POST-1846-A. HERRYWEATHER D.S. (IRONWOOD 10°-N50°E-14 LINKS) (SUGAR MAPLE 20°-S23°W-16 LINKS)  
M.S. McNABB - 1914 - NO EVIDENCE OF ORIGINALS FOUND - ESTABLISHED BETWEEN CORNERS  
SET IRON STAKE - FENCE POST S76°30'W 44.8'

C-1 [NW COR SEC 5] WOOD POST-1844-JOHN BURT D.S. (HEMLOCK 14°-N75°E-27 LINKS) (Y. BIRCH 16°-N49°W-24 LINKS)  
A. HERRYWEATHER D.S. - 1846 - (HEMLOCK 14°-S24°E-17 LINKS) (HEMLOCK 7°-S20°W-4 LINKS)  
C.E. BROTHERTON - 1884 - ORIGINALS IN PLACE - NO NEW WIT'S NOTED  
M.S. McNABB - 1914 - ID FROM REMAINS OF ORIGINAL BT - BT STAKES NE & SW 33'  
M.S. McNABB - 1919 - SET IRON STAKE - BT STAKES IN PLACE  
M. DAVIS - 1977 - L.C.R.'S, IN LIBER 2 PAGE 147

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-7 [1/4 COR COMMON TO SEC'S 18/19] McNABB'S IRON STAKE APPARENTLY DESTROYED IN ROAD CONSTRUCTION - FOUND McNABB'S 1918 C1/4 & CS1/16 OF SEC 13 & EXTENDED LINE S FROM C1/4 THRU CS1/16 & SET 1/4 COR ON THIS LINE A PROPORTIONATE DISTANCE S. OF CS1/16  
ACCEPTED THIS POSITION AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

C-1 [NW COR SEC 5] FOUND MONUMENT AS SET BY MYSELF IN 1977 & DESCRIBED AT L.C.R.'S, IN LIBER 2 PAGE 147  
ACCEPTED AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 REPLACED EXISTING MON W/A 5/8" X 18" REBAR W/A ALUMN CAP & RAISED TO RD SURFACE W/A MONUMENT BOX  
POWER POLE POWER POLE C.L. COUNTY ROAD 525  
S85°W S82°E WEST  
38.00' 23.83' 5.5'

B-7 SET BERNSEN AINB30 ALUMN MONUMENT W/A 3-1/4" CAP STAMPED TO ID THE COR POSITION  
POWER POLE COR FENCE POST SURVEY MONUMENT SIGN POST  
N37°W S79°W S45°W  
46.03' 24.36' 1.40' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. DAVIS

Date 11/15/93

Surveyor's Michigan License No. 16926