

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Class. R.O., 1994

Robert Schulz
Acting Chairman

For corners in

DELTA

(County)

Located In:

Corner Code #/

1. Public Land Survey	T	40	N	R	23	W	D-3 & D-9
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Recorded January 21, 1994

at 10:00 o'clock a.m. in Liber 7 Page 376

Walter C. ... Reg. of Deeds,
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims D-3 [N1/4 COR SEC 8] D-9 [N1/4 COR SEC 29]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		•										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		•										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on JULY, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- D-3 [N1/4 COR SEC 8] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (BURNT TAMERAC 6°-S88°W-7 LINKS) (BURNT TAMERAC 10°-S86°E-48 LINKS) M.S. McNABB - 1929 - NO EVIDENCE OF ORIGINALS - SET WOOD POST MARKED "1/4" AT HALF DISTANCE BETWEEN CORNERS (W. BIRCH 6°-N80°E-7.3')
 - D-9 [N1/4 COR SEC 29] WOOD POST - A. MERRYWEATHER - 1846 (MAPLE 12°-S60°W-11 LINKS) (MAPLE 22°-N10°E-19 LINKS) M.S. McNABB - 1920 - FOUND IRON BOLT IN PLACE - FENCE POST N & S 25.5'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- D-3 [N1/4 COR SEC 8] FOUND, THIS DATE ON THE WESTERLY EDGE OF WOODS ROAD (NE-SW) AND AT THE JCT OF FENCE LINES N & W A SQ'D WOOD POST SCRIBED "1/4". ACCEPTED THIS CORNER POSITION AS BEING A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.
 - D-9 [N1/4 COR SEC 29] IRON BOLT FOUND BY McNABB IN 1920 HAS APPARENTLY BEEN DESTROYED BY ROAD CONSTRUCTION. REPLACED SAME BY RETRACEMENT OF McNABB'S 1920 SURVEY OF THE N-S1/4 LINE OF SEC 29. FD S1/4 COR SEC 29 & McNABB'S I.P. AT THE CS1/16 EXTENDED LINE NORTH FROM THE S1/4 COR AND THRU THE CS1/16 AND SET N1/4 COR SEC 29 ON THIS LINE AND AT PROPORTIONATE DISTANCE (BASED ON COMPARISON OF McNABB'S 1920 DISTANCES) NORTH OF THE E-W 1/4 LINE.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- D-3 REPLACED WOOD POST W/A BERNTSEN ALUMN MON WITH THE CAP STAMPED TO ID THE CORNER POSITION

CEDAR 9"	CEDAR 8"	TAMARACK 7"	TAMARACK 6'	SURVEY MONUMENT SIGN POST
N66°W	N82°E	S32°E	S43°W	WEST
16.00'	16.30'	39.60'	23.60'	3.20' (TO FACE)
 - D-9 SET, INSIDE MON BOX, A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TOP ID THE CORNER POSITION

RED PINE 5"	POWER POLE	POWER POLE	SURVEY MONUMENT SIGN POST
S65°W	N17°E	S66°E	SOUTH
66.42'	24.28' (TO FACE)	98.00' (TO FACE)	24.59' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 12/29/93

Surveyor's Michigan License No. 16926