

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On October 21, 1993  
*Robert E. Schumaling*  
Acting Chairman

For corners in

DELTA

(County)

Located In:

Corner Code 44

- 1. Public Land Survey T 39 N R 23 W D-1 & E-2  
T \_\_\_\_\_ R \_\_\_\_\_  
T 40 N R 23 W D-13  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

DELTA COUNTY

LIBER 7 PAGE 315

93 DEC -2 AM 9:00

*Wallace C. Thoreau*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

1/4 COR SEC 5 & 1/4 COR COMMON TO SEC 5/4

SAME AS D-13 T 40 N R 23 W

I, M.P. DAVIS, in a field survey on AUGUST, 19 93,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D-1 [1/4 COR SEC 5] JOHN BURT-1845-WOOD POST - FIR-N20°E 8 LINKS - Y. BIRCH N32°W-24 LINKS  
M.S. McNABB -1920-STAKE IN PLACE - CEDAR STUMP 24°-N75°E-22.5' - CEDAR STUMP 20°-N82°W-31.3'

E-2 [1/4 COR COMMON TO SEC'S 5/4] A. MERRYWEATHER-1846-WOOD POST - CEDAR 18°-NORTH-24 LINKS - CEDAR 14°-S20°E-6 LINKS  
M.S. McNABB-1925-IRON STAKE IN PLACE-FENCE POST-N60°W-28' - FENCE POST-EAST-15.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 FOUND IRON PIPE AS DESCRIBED IN LIBER 2 OF L.C.R.'S. ON PAGE 143 - ACCEPTED EXISTING MONUMENT AS A FAITHFUL & CAREFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

E-2 FOUND IRON PIPE AS DESCRIBED IN LIBER 2 OF L.C.R.'S. ON PAGE 143 - ACCEPTED EXISTING MONUMENT AS A FAITHFUL & CAREFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 SET 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION INSIDE OF EXISTING I.P. (6" BELOW ROAD SURFACE)  
ELM 22" TAMARACK 7" CUT ON E. END CMP X-PIPE SURVEY MONUMENT SIGN POST  
N8°W S62°W S40°E EAST  
33.00' 63.74' 29.12' 18.9' (TO FACE)

E-2 SET 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION INSIDE OF EXISTING I.P. (6" BELOW ROAD SURFACE)  
POWER POLE POWER POLE SURVEY MONUMENT SIGN POST  
N43°W N52°E EAST  
32.62' (TO FACE) 31.60' 12.90' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. Davis

Date 10/10/93

Surveyor's Michigan License No. 16926

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6			5	4			3		2			1
3													
4	7			8	9			10		11			12
5													
6	18			17	16			15		14			13
7													
8	19			20	21			22		23			24
9													
10	30			29	28			27		26			25
11													
12	31			32	33			34		35			36
13													

