

FEB 18 1994

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Jan. 20, 1994 Robert Behmeling Acting Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in DELTA (County) Located In: Corner Code # 1. Public Land Survey T 40 N R 23 W F-9 & G-11 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R 4. Lot No. , Recorded Plat 5. Private Claims F-9 [N1/4 COR SEC 28] G-11 [NW COR SEC 34]

Recorded January 21, 1994 at 9:00 o'clock a.m. Liber 7 Page 381 Register of Deeds Stamp & File Number

I, M.P. DAVIS in a field survey on JULY 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the cornerpoints mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numerical data points for survey locations.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: F-9 [N1/4 COR SEC 28] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (MAPLE 26'-S60°W-32 LINKS) (MAPLE 12"-S34°E-31 LINKS) D.A. BROTHERTON - 1895 - IDENTIFIED CORNER FROM BOTH ORIGINAL - SET NEW STAKE - NO NEW WIT'S NOTED M.S. McNABB - 1932 - IDENTIFIED FROM STAKE IN INTERSECTION OF ROADWAYS NORTH & EAST - SET IRON STAKE CORNER FENCE POST N50°W-34' ELM SHADE TREE 16"-S10°W-36'

G-11 [NW COR SEC 34] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (CEDAR 8"-S15°W-20 LINKS) (CEDAR 8"-N32°E-25 LINKS) C.E. BROTHERTON - IDENTIFIED FROM ORIGINALS - DATE UNKNOWN (FROM NOTES OF D.A. BROTHERTON) D.A. BROTHERTON - 1895 - IDENTIFIED FROM STAKE IN PLACE (FENCE PSOT N34°10'E-29.45') (FENCE POST-N33°45'W-29.3') (FENCE POST-S37°W-41') REPLACED STAKE WITH IRON BOLT D.A. BROTHERTON - 1910 IDENTIFIED CORNER FROM IRON BOLT & BT'S SET PREVIOUS

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: F-9 [N1/4 COR SEC 28] FOUND IRON PIN 36" BELOW ROAD SURFACE FROM WHICH A ELM STUMP (DETERIORATED & IN POOR CONDITION) BEARS S10°W-36'. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER POSITION.

G-11 [NW COR SEC 34] FOUND IRON PIN 15" BELOW COUNTY ROAD SURFACE - NO EVIDENCE OF BROTHERTON'S 1910 WIT'S - DISTANCE SOUTH TO SW COR SEC 34 CORRESPONDS WELL WITH BROTHERTONS DISTANCE. ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: F-9 SET OVER EXISTING MON A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON BOX DRILL HOLE IN FIELD STONE POWER POLE POWER POLE SURVEY MONUMENT SIGN POST N11°W N53°E S66°E SOUTH 40.17' 34.00' (TO FACE) 101.36' (TO FACE) 22.10' (TO FACE)

G-11 SET OVER EXISTING MON A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON BOX ELM 7" POWER POLE COR FENCE POST SURVEY MONUMENT SIGN POST N10°W S18°E S42°W N45°E 79.28' 44.83' 52.82' 20.15' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 12/29/93

Surveyor's Michigan License No. 16926