

FEB 18 1994

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Jan. 20, 1994

Robert Schmeling Acting Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code =#

- 1. Public Land Survey T 40 NR 23 W K-1 & K-2
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

Recorded January 21, 1994 at 9:00 o'clock a.m. in Liber 7 Page 361 Walter C. Thomas Reg. of Deeds, Delta County, Michigan Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims K-1 [NW COR SEC 1] K-2 [W1/4 COR SEC 2]

I, M.P. DAVIS, in a field survey on JULY, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. Contains numerical data for survey points.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1 [NW COR SEC 1] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (CEDAR 18"-S72°E-16 LINKS) (SPRUCE 9"-S80°W-44 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT RECOVERY OR RESTORATION OF THE CORNER POSITION
K-2 [W1/4 COR SEC 1] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (HEMLOCK 12"-S73°W-17 LINKS) (HEMLOCK 20"-N18°E-21 LINKS) NO RECORD EVIDENCE OF SUBSEQUENT RECOVERY OR RESTORATION OF THE CORNER POSITION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-1 [NW COR SEC 1] NO EVIDENCE OF THE ORIGINALS FOUND - MR. OTTO DAHN (NOW DECEASED) SHOWED ME AN IRON PIPE & A SQ'D POST IN 1971 AND STATED THAT HE WAS A LIFE LONG RESIDENCE OF THE AREA & TO THE BEST OF HIS RECOLLECTION THE CORNER POST ALWAYS STOOD IN THE LOCATION SHOWN TO ME. RAN 4TH CORRECTION LINE NORTH (S LINE SEC 31 T41N R22W) AND FOUND EXISTING MON 8.33' SOUTH OF THE CORRECTION LINE. ESTABLISHED NEW COR ON THE CORRECTION LINE WITH IT'S INTERSECTION WITH THE NORTH PROJECTION OF THE SW COR OF SEC 1 & THE NW COR OF SEC 1 AS SHOWN TO ME BY MR. DAHN.
K-2 [W1/4 COR SEC 1] NO EVIDENCE OF ORIGINALS FOUND - ESTABLISHED 1/4 COR ON LINE AND PROPORTIONATE DISTANCE BETWEEN SEC CORNERS NORTH & SOUTH



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-1 SET 4" X 4" X 36" CONCRETE MONUMENT W/A BRASS CAP STAMPED TO ID THE CORNER POSITION
ASH 8" CEDAR 7" CEDAR 8" SURVEY MONUMENT SIGN POST NOTE: BE AWARE OF LARGE LOCAL ATTRACTION OF COMPASS NEEDLE.
N4°W N77°E S34°W S12°E
11.91' 29.89' 64.30' 2.47' (TO FACE)
K-2 SET 4" X 4" X 36" CONCRETE MONUMENT W/A BRASS CAP STAMPED TO ID THE CORNER POSITION
WHITE BIRCH 14" WHITE PINE 12" SPRUCE 17" SURVEY MONUMENT SIGN POST
N12°W S76°E S86°W S39°E
65.10' 27.60' 27.00' 1.73' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 12/30/93
Surveyor's Michigan License No. 16926