

**SURVEY & REMONUMENTATION**

OCT 03 2000

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 of

P.A. of 1990 On July 12, 2000

Robert Schmeling  
 Acting Chairman

For corners in

<u>DELTA</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>40</u> N R <u>23</u> W	<u>K-03</u>
	T <u>40</u> N R <u>23</u> W	<u>K-06</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECORDED 28 July 2000  
 AT 9:00 O'CLOCK a.m.  
 LIBER 9 PAGE 222  
Walter C. Flannery  
 DELTA COUNTY MI REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, M.P. DAVIS, in a field survey on MAY, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K-03 [NW COR SEC 12] A.MERRYWEATHER, D.S. -1846-SET POST-(BEECH 05" S60°E 07 LINKS)(CEDAR 10" NORTH 10 LINKS) D.A.BROTHERTON - 1895 - ORIGINALS IN PLACE NOTED NEW BT'S (Y.BIRCH 10" N13°W 66.3')(B.ASH 5" N59°W 42') M.S.McNABB - -1932 - FOUND IN PLACE FROM PREVIOUS SURVEYS - W.PINE 8" S18°E 60.0' - NO DESCRIPTION OF MONUMENT GIVEN M.DAVIS - 1973 - L.1 OF LCR'S PG 335 - FD IRON PIN IN PLACE (PP S8°E 43.6')(PP N80°E 74.9')(PP N66°W 114.3') M.DAVIS - 1976 - L.2 OF LCR'S PG 84 - ID MONUMENT AS MENTIONED ABOVE & AT THIS TIME HAD ACQUIRED THE RECORDS OF M.S.McNABB WHICH REFERENCED TO A W.PINE BT TO THE SE WHICH IS STILL GREEN & CHECKS WELL TO THE EXISTING MONUMENT.
- K-06 [W1/4 COR SEC 13] A. MERRYWEATHER, D.S. 1846 - (HEMLOCK 14" S40°E 20 LINKS) (HEMLOCK 24" N11°W 45 LINKS M.S.McNABB-1944 - STAKE IN PLACE - HEMLOCK 9" N42°E 66'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-03 [NW COR SEC 12] FOUND IN PLACE AND 24"± BELOW THE ROAD SURFACE A 3/4" IRON PIN AS PREVIOUSLY RECOVERED. ID EXISTING MONUMENT FROM THE W.PINE BT TO THE SE WHICH IS STILL GREEN. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFULL PERPETUATION OF THE POSITION IF THE ORIGINAL CORNER.
- K-06 [W1/4 CCR SEC 13] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION ON LINE WITH AND AT THE MIDPOINT BETWEEN SECTION CORNERS 1/2 MILE NORTH AND SOUTH.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-03 PLACED, OVER EXISTING MON, A 5/8" X 18" REBAR W/A ALUM CAP STAMPED TO ID THE COR POSITION & RAISED TO GRADE WITH A MON BOX.  
 SURVEY MONUMENT SIGN POST      CEDAR 09"      CEDAR 10"      W.PINE 24" (OLD BT)  
 NORTH      N31°E      S70°W      S18°E  
 23.36' (TO FACE)      61.35'      86.58'      60.10'
- K-06 SET A 5/8" X 18" REBAR W/A 3-1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MON BOX  
 SURVEY MONUMENT SIGN POST      POWER POLE      5/8" X 18" REBARS W/A 2" ALUM DELTA COUNTY WITNESS CAP  
 N83°W      S81°E      N45°W      S45°W  
 21.93' (TO FACE)      27.75'      28.08'      30.88'

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC-DISTANCES ARE TO A NAIL W/A DELTA COUNTY REFERENCE TAG, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis  
 Surveyor's Michigan License No. 16926

Date 7/13/00