

SURVEY & REMONUMENTATION

FEB 18 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On Jan. 20, 1994

Robert K. Schueling
 Acting Chairman

For corners in
DELTA
 (County)

Located In:

Corner Code =#

1. Public Land Survey	T	40 N R	23 W	L-7 & G-9
	T	___ R	___	___
	T	___ R	___	___
	T	___ R	___	___
2. Property Controlling in Section	S	___ T	___ R	___
	S	___ T	___ R	___
3. Miscellaneous Property in Sec.	S	___ T	___ R	___
	S	___ T	___ R	___

Recorded January 21, 1994

9:00 a.m. in Lib 7 Page 364

Walter C. Darrow Reg. of Comm.
 Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims
 L-7 [N1/4 COR SEC 24] G-9 [NW COR SEC 27]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on JULY, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 L-7 [N1/4 COR SEC 24] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (CEDAR 12°-N29°E-20 LINKS) (HEMLOCK 15°-S75°W-27 LINKS)
 M.S. McNABB - 1915 - FOUND STAKE IN CLEARING - 1944 FOUND STAKE FROM PREVIOUS SURVEY & NOW I.P. ALONG SIDE - NO WIT'S AVAILABLE
 G-9 [NW COR SEC 27] WOOD POST - A. MERRYWEATHER, D.S. - 1846 (CEDAR 9°-S35°E-17 LINKS) (S PINE 10°-N26°W-14 LINKS)
 D.A. BROTHERTON - 1895 - ID CORNER POSITION FROM "GLO" CEDAR BT - SET NEW STAKE & NERW BT'SD (CEDAR 14°-S64°20'W-31.5') (CEDAR 16°-N26°50'W-66.9')
 M.S. McNABB - 1931 - FOUND STAKE & SET I.P. - CEDAR STUMP 18°-S12°E-23'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 L-7 [N1/4 COR SEC 24] FOUND I.P. & WOOD POST SCRIBED "1/4" NO EVIDENCE OF McNABB'S POPPLE BT LINE AND DISTANCE EAST TO E1/16 & SEC CORNER CHECKS WELL WITH McNABB'S SURVEY. ACCEPTED EXISTING MONUMENT AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER
 G-9 [NW COR SEC 27] FOUND I.P. IN PLACE AS INDICATED BY OCCUPATION & ROAD IMPROVEMENTS - NO EVIDENCE OF McNABB'S CEDAR STUMP BT - EXISTING MONUMENT CHECKS WELL WITH McNABB'S MEASUREMENTS TO ADJOINING CORNERS. ACCEPTED EXISTING MONUMENT AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 L-7 SET, OVER EXISTING I.P., A BERNTSEN ALNB30 ALUMN MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION SURVEY MONUMENT SIGN POST NOTE: CORNER IS NEAR EASTERLY EDGE OF OPEN FIELD & 10' M. OR L. SOUTH OF THE C.L. OF A E-W WOODS ROAD NO WIT'S ARE AVAILABLE
 S45°W 1.48' (TO FACE)
 G-9 SET OVER EXISTING MON A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE COR POSITION & RAISED TO RD SURFACE W/A MON BOX
 CEDAR 9" CEDAR 7" CEDAR 5" CEDAR 5" SURVEY MONUMENT SIGN POST
 N45°W N57°E S50°E S40°W NORTH
 58.25' 66.78' 62.56' 40.83' 28.12' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED

Signed by M.P. Davis Date 12/30/93
 Surveyor's Michigan License No. 16926