

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On May 19, 1994
Robert Schmeling
Acting Chairman

For corners in
DELTA
(County)

Located In: Corner Code #

- 1. Public Land Survey T 39 N R 24 W A-1 & A-2
T 40 N R 24 W A-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Recorded JUN - 8 1994
at 9:00 o'clock AM in Liber 8 Page 2
Walter C. Moran Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

A-1 [NW COR S.6] A-2 [W1/4 COR S.6]
SAME AS M-1, M-2 T39N R25W (MENOMINEE COUNTY)
SAME AS A-13 T40N R24W (DELTA COUNTY)

I, M.P. DAVIS, in a field survey on MAY 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 6 through 36.

- A. Description of original monument and accessories and/or subsequent restoration:
A-1 [NW COR S.6] JAMES H. MULLETTE, D.S. - 1848 - WOOD POST (BIRCH 15"-N35°W-35 LINKS) (BIRCH 14"-S60°W-35 LINKS)
M.S. McNABB - 1918 - IDENTIFIED FROM ORIGINAL NW BIRCH BT - SET NEW STAKE (CEDAR STUMP 20"-S70°E-15.0')
M.S. McNABB - 1920 - FROM PREVIOUS SURVEY - (CORNER FENCE POST-WEST-20.9') (FENCE POST-EAST 25')
A-2 [W1/4 COR S.6] JAMES H. MULLETTE, D.S. - 1848 - WOOD POST (LYNN 14"-S71°W-09 LINKS) (LYNN 24"-N41°W-14 LINKS)
M.S. McNABB - 1920 - IRON BOLT IN PLACE (CORNER FENCE POST-WEST-17') (FENCE POST-EAST-28')

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
A-1 [NW COR S.6] FOUND IN PLACE McNABB'S 1920 IRON PIPE, 24" M/L BELOW EXISTING ROAD SURFACE. IDENTIFIED CORNER POSITION BY EXISTING E-W OCCUPATION & N-S COUNTY ROAD IMPROVEMENTS AND COMPARISON OF McNABB'S MEASUREMENTS TO ADJOINING CORNERS. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
A-2 [W1/4 COR S.6] FOUND IN PLACE AN IRON BOLT AS MENTIONED IN THE 1920 SURVEY RECORDS OF M.S. McNABB. HIS ACCESSORIES TO THE CORNER WERE APPARENTLY REMOVED IN COUNTY ROAD IMPROVEMENTS. IDENTIFIED CORNER POSITION BY EXISTING OCCUPATION TO THE WEST & N-S COUNTY ROAD IMPROVEMENTS AND COMPARISON OF McNABB'S MEASUREMENTS TO ADJOINING CORNERS. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-1 SET OVER EXISTING MON & 6" M/L BELOW RD SURFACE A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
RED PINE 8" W. BIRCH 7" CHISELED "X" ON LARGE FIELD STONE SURVEY MONUMENT SIGN POST
N32°E S65°E S42°E WEST
50.20' 36.80' 34.70' 21.67' (TO FACE)
A-2 SET OVER EXISTING MON & 6" M/L BELOW RD SURFACE A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
MAPLE 14" POWER POLE SURVEY MONUMENT SIGN POST NOTE: OPEN FARM FIELD IN THE NW & SW QUADS
N59°E S24°E WEST NO OTHER WIT'S AVAILABLE.
53.70' 54.32'(TO FACE) 19.68' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 5/4/94
Surveyor's Michigan License No. 16926