

**SURVEY & REMONUMENTATION**

9/99

NOV 25 1998

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On Sept 25, 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

*Robert Schmelting*  
Acting Chairman

For corners in  
**DELTA**  
(County)

Located In:

Corner Code #

- |                                    |                             |                      |
|------------------------------------|-----------------------------|----------------------|
| 1. Public Land Survey              | T <u>40 N</u> R <u>24 W</u> | <u>G-1 &amp; G-2</u> |
|                                    | T _____ R _____             | _____                |
|                                    | T _____ R _____             | _____                |
|                                    | T _____ R _____             | _____                |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____                |
|                                    | S _____ T _____ R _____     | _____                |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____                |
|                                    | S _____ T _____ R _____     | _____                |

Recorded SEP 28 1998  
at 9:00 o'clock A.M.  
Liber 9 Page 99  
*Wallace C. Thorne*  
Delta County, MI Reg. of Deeds  
**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims G-1 [NW COR SEC 3] G-2 [W1/4 COR SEC 3]

NOTE: NOT COMMON WITH TWP. 75 NORTH

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on AUGUST 27, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G-1 [NW COR SEC 3] WOOD POST H. MILLEN D.S. 1852 (CEDAR 09" -S28°W-09 LINKS)(CEDAR 08"-S84°E-09 LINKS)  
NO RECORD EVIDENCE OF CORNER RECOVERY AND/OR SUBSEQUENT REMONUMENTATION

G-2 [W1/4 COR SEC 3] WOOD POST H.MILLEN D.S. 1852 (SPRUCE 18"-N31°E-26 LINKS)(CEDAR 16"-S06°W-26 LINKS)  
NO RECORD EVIDENCE OF CORNER RECOVERY AND/OR SUBSEQUENT REMONUMENTATION

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

G-1 [NW COR SEC 3] FOUND IN PLACE A POST POINT & THE REMAINS OF A BADLY CHARRED SQUARED CEDAR POST AND THE REMAINS OF A BADLY DECAYED CEDAR STUMP (NO IRON MARKS VISIBLE) TO THE SW WHICH CLOSELY MATCHES THE BEARING & DISTANCE OF THE SW "GLO" BT. ALSO FOUND IN PLACE THE REMAINS OF A SQUARED CEDAR POST WEST 29.60' ("GLO" 29.7') REPRESENTING THE SW COR OF SEC 36 T41N R24W. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL COR.

G-2 [W1/4 COR SEC 3] NO CORNER EVIDENCE FOUND. CORNER POSITION FALLS IN THE CLEARED R/W OF A RECENTLY CONSTRUCTED E-W ELECTRICAL TRANSMISSION LINE. RESTORED CORNER POSITION ON A STRAIGHT LINE WITH AND PROPORTIONATE DISTANCE BETWEEN SEC CORNERS 1/2 MILE N & S.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

G-1 REPLACED WOOD POST W/A BERNTSEN AINB36 ALUMN MONUMENT W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
CEDAR 7" ASH 15" SW COR SEC 36 T41N R24W SURVEY MONUMENT SIGN POST  
N25°W S05°E WEST NORTH  
66.81' 37.65' 29.60' 1.23 TO FACE

G-2 SET A BERNTSEN AINB30 ALUM MON W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.  
SPRUCE 07" GATE POST CORNER FENCE POST C/L E-W ELECTRIC LINE SURVEY MONUMENT SIGN POST  
N18°E S44°E S44°W NORTH NORTH  
53.47' 52.40' 43.53' 11.5' 1.88' TO FACE

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 9/22/96

Surveyor's Michigan License No. 16926