

SURVEY & REMONUMENTATION

JAN 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/18, 1992

Robert Behmeling
Acting Chairman

For corners in
DELTA

| | | | |
|------------------------------------|---------------------------|----------------|--|
| | Located In: | Corner Code # | |
| (County) | | | |
| 1. Public Land Survey | T <u>10N</u> R <u>24W</u> | <u>G-4</u> H-5 | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |

Dec 19 1997
9:00 AM
28 264

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
G-4 [1/4 COR COMMON TO SEC'S 9/10] H-5 [1/4 COR COMMON TO SEC'S 10/15]

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- G-4 [1/4 COR COMMON TO SEC'S 9/10] WOOD POST H. MILLEN D.S. 1852 (TAMARACK 12" -S15°E-17 LINKS)(TAMARACK 12"-N88°W-32 LINKS) MEAD PAPER COMPANY WOODLAND DEPT. 1970 - ID ORIGINAL TAMARACK WITNESSES - SET WOOD POST FROM SAME - CEDAR S2°E 11.6'
 - H-5 [1/4 CORNER COMMON TO SEC'S 10/15] WOOD POST H.MILLEN D.S. 1952 (CEDAR 14"-S75°W-27 LINKS)(CEDAR 16"-S93°E-30 LINKS) M.P. DAVIS 1988 - SET 5/8" X 18" REBAR WITH AN ALUMN CAP ON NORTH EDGE OF COUNTY ROAD - ESTABLISHED FROM EXISTING OCCUPATION LINES AND ROAD IMPROVEMENTS. NO WITNESSES LISTED.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- G-4 [1/4 COR COMMON TO SEC'S 9/10] FOUND THIS DATE WOOD POST AND MEAD WOODLANDS CEDAR WITNESS. ALSO POSSIBLE REMAINS OF ORIGINAL TAMARACK WITNESSES NOW WELL DECAYED STUMPS. ACCEPTED EXISTING MONUMENT AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.
 - H-5 [1/4 COR COMMON TO SEC'S 10/15] FOUND THIS DATE DAVIS 1988 REBAR AND ALUMN CAP - CAP BADLY DAMAGED BY ROAD GRADING. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- G-4 REPLACED WOOD POST W/A BERNTSEN AINB36 ALUMN MONUMENT W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

| | | | | | |
|----------|----------|----------|----------|---------------------------|-------------------------|
| CEDAR 8" | CEDAR 9" | CEDAR 5" | CEDAR 8" | SURVEY MONUMENT SIGN POST | FENCE CORNER |
| N68°E | S54°E | S61°W | N72°W | NORTH | 13.37 EAST & 2.30 SOUTH |
| 18.55' | 24.70' | 19.07' | 21.95' | 1.81 TO FACE | |
 - H-5 RECAPPED EXISTING 5/8" X 18" REBAR (6" BELOW GRADE) W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.

| | | | | |
|----------|-----------|-----------|----------|---------------------------|
| MAPLE 8" | MAPLE 12" | CEDAR 11" | CEDAR 5" | SURVEY MONUMENT SIGN POST |
| N30°E | S69°E | N78°W | S15°E | NORTH |
| 37.27' | 21.34' | 28.10' | 25.43' | 1.88' TO FACE |

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/4/97
Surveyor's Michigan License No. 16926