

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Sept 25, 1998
Robert E. Schueling, Acting Chairman

For corners in DELTA (County)

Located In: Corner Code ##

- 1. Public Land Survey T 40 N R 24 W H-1 & J-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Recorded SEP 28 1998 at 9:00 o'clock A.M. Liber 9 Page 100
Walter C. Thorne, Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims H-1 [N1/4 COR SEC 3] J-1 [N1/4 COR SEC 2]

NOTE: NOT COMMON WITH TWP TO NORTH

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 and markers for H-1 and J-1.

I, M.P. DAVIS, in a field survey on SEPTEMBER 02, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-1 [N1/4 COR SEC 3] NOT SET IN ORIGINALS
NO RECORD EVIDENCE OF CORNER MONUMENTATION

J-1 [N1/4 COR SEC 2] NOT SET IN ORIGINALS
M.S. McNABB 1920 - SET STAKE "1/2 DISTANCE" BETWEEN SEC COR'S & 65.5' WEST OF S1/4 COR SEC 31 T41N R23W-NO WIT'S NOTED.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-1 [N1/4 COR SEC 3] NO CORNER EVIDENCE FOUND, ESTABLISHED CORNER POSITION ON 4TH CORRECTION LINE AND AT MIDPOINT BETWEEN SEC COR'S 1/2 MILE EAST & WEST.

J-1 [N1/4 COR SEC 2] NO CORNER EVIDENCE FOUND. REESTABLISHED CORNER POSITION ON 4TH CORRECTION LINE 65.5' WEST OF THE S1/4 COR OF SEC 31 T41N R23W AS PER THE REDCORDS OF McNABB. CORNER POSITION FALLS IN LINE WITH ANCIENT FENCE LINE (DOWN & IN POOR REPAIR) TO THE SOUTH.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

H-1 SET A BERNTSEN AINB36 ALUMN MONUMENT W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 10" CEDAR 12" S1/4 COR SEC 36 T41N R24W SURVEY MONUMENT SIGN POST
S76°E S56°W WEST SOUTH
17.32' 7.35' 39.96' 2.12 TO FACE

J-1 SET, 6" BELOW GRADE, A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION.
CEDAR 11" SPRUCE 12" MAPLE 96" BALSAM 07" SURVEY MONUMENT SIGN POST
N53°W N13°E S25°E S53°W SOUTH
94.37' 57.45' 48.95' 57.70 26.80' TO FACE

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 9/22/98
Surveyor's Michigan License No. 16926