

SURVEY & REMONUMENTATION

JAN 14 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/18, 1992
Robert E. Schmalz
Acting Chairman

For corners in
DELTA

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>40N</u>	R <u>24W</u>	J-5
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Dec 19 1997
9:00 AM
8 273
Robert E. Schmalz

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims
J-5 [1/4 COR COMMON TO SEC'S 11/14]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on NOVEMBER, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-5 [1/4 COR COMMON TO SEC'S 11/14] WOOD POST H. MILLEN D.S. 1852 (HEMLOCK 12" -N21°W-13 LINKS)(SUGAR 12"-S35°E-27 LINKS) M.S. MCNABB 1918 - NO EVIDENCE OF ORIGINALS FOUND - RESET STAKE AT 1/2 DISTANCE BETWEEN SEC COR'S EAST & WEST (BT STAKES NE & SW 33 FEET) M.P. DAVIS 1986 - NO EVIDENCE OF MCNABB'S STAKE OR BT STAKES - SET 3/4" X 18" IRON PIPE AT MIDPOINT AND ON LINE BETWEEN SEC COR'S 1/2 MILE EAST AND WEST - NO WITNESSES LISTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
J-5 [1/4 COR COMMON TO SEC'S 11/14] FOUND THIS DATE DAVIS 1986 IRON PIPE - DISTANCE TO SEC COR'S 1/2 MILE EAST & WEST MATCHES WELL WITH RECORDS OF MCNABB. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
J-5 REPLACED IRON PIPE W/A 5/8" X 18" REBAR W/A 3 1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MONUMENT BOX.

MAPLE 5"	BALSAM 4"	MAPLE 7"	BALSAM 5"	SURVEY MONUMENT SIGH POST
N33°E	S29°E	N07°W	S55°W	NORTH
40.53'	46.94'	35.05'	66.93'	16.00 TO FACE

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG UNLESS OTHERWISE NOTED.

Signed by *M.P. Davis* Date 12/14/97
Surveyor's Michigan License No. 16926