

SURVEY & REMONUMENTATION

NOV 25 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On Sept 25, 1998

Robert E. Schmeling
Chairman

For corners in

DELTA
(County)

Located In:

Corner Code ##

- | | | |
|------------------------------------|-----------------------------|------------|
| 1. Public Land Survey | T <u>40</u> N R <u>24</u> W | <u>L-5</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded SEP 28 1998
at 9:00 o'clock A.M.
Liber 9 Page 101
William C. Thoren
Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims L-5 [N1/4 COR SEC 13]

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, M.P. DAVIS, in a field survey on SEPTEMBER, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-5 [N1/4 COR SEC 13] HARVEY MILLEN, D.S. - 1852 - WOOD POST - (HEMLOCK 06°-N40°W-02 LINKS) (HEMLOCK 06°-S80°W-22 LINKS)
M.S. McNABB-1913- ROAD ALIGNMENT SURVEY FOR CORNELL TWP. - ID CORNER POSITION FROM BOTH ORIGINALS- SET BY STAKES NE & SW 33'
M. DAVIS-1974-RESTORED CORNER POSITION FROM RETRACEMENT OF McNABB'S 1913 ROAD ALIGNMENT SURVEY-SET TRACK SPIKE-FENCE POST S3°E 29.9'
C/L PP S47°W 40.2' C/L UTILITY POLE N10°E 58.6' REC'D LIBER 2 PAGE 86.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-5 [N1/4 COR SEC 13] FOUND TRACK SPIKE AS SET BY MYSELF IN 1974. ID CORNER MONUMENT FROM MEASUREMENTS EAST & WEST TO ADJOINING CORNERS. ALL 1974 ACCESSORIES HAVE BEEN REMOVED OR DESTROYED. ACCEPTED THIS POSITION AS A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-5 REPLACED EXISTING MON W/A 5/8" X 18" REBAR W/A 3-1/4" ALUMN CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MON BOX SURVEY MONUMENT SIGN POST 5/8" X 18" REBAR W/A 2" ALUM WIT CAP
SOUTH N45°W S45°W
25.75' (TO FACE) 24.65' 27.60'

NOTE: FARM FIELDS IN SE & SW QUADRANTS, RESIDENTIAL YARD IN THE NE QUADRANT & 2ND GROWTH TIMBER IN THE NW QUADRANT

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL W/A REFERENCE TAG, UNLESS NOTED OTHERWISE

Signed by M.P. Davis 9/22/98 Date _____

Surveyor's Michigan License No. 16926