

REMONUMENTATION

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Sept 22, 1993
Acting Chairman

For corners in DELTA (County)

Table with columns: Located In: (41 N, 18 W), Corner Code # (C-11, C-12), and rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Recorded Oct 1, 1993 at 9:00 o'clock AM in Liber 7 Page 310
William C. Thayer Reg. of Deeds. Delta County, Michigan

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13, containing numbers 6-36 and a dot in cell 11B.

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-11 [NW COR SEC 32] WOOD POST A. MERRYWEATHER 1849 (CEDAR 10°-N40°W-19 LINKS) (SPRUCE 12°-S20°E-10 LINKS) M.S. McNABB-JANUARY 1920-IDENTIFIED GLO CEDAR BT NW-RESET CEDAR STAKE AT FENCE CORNER NO NEW WITNESSES NOTED.
C-12 [1/4 COR COMMON TO SEC'S 31/32] WOOD POST-A. MERRYWEATHER 1849 (BALSAM 7°-N44°W 23 LINKS) (BALSAM S40°E 5 LINKS) M.S. McNABB-JANUARY 1920-NO ORIGINAL EVIDENCE FOUND-ESTABLISHED 1/4 CORNER HALF DISTANCE BETWEEN CORNERS. SET CEDAR POST (CEDAR 3°-S50°E-16.9') (CEDAR 3° N55°W-8.5')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-11 [NW COR SEC 32] FOUND THIS DATE McNABB'S 1920 SCRIBED CEDAR POST AT JCT OF FENCE LINES SOUTH & WEST. THE CORNER MONUMENT FOUND IS ACCEPTED AS A CAREFUL & FAITHFUL PERPETUATION OF POSITION OF THE ORIGINAL CORNER.
C-12 [1/4 CORNER COMMON TO SEC'S 31/32] FOUND THIS DATE McNABB'S CEDAR BT (N55°W-8.5') SCRIBE MARKS CLEAR - REPLACED 1/4 CORNER FROM SAME. THIS CORNER POSITION IS ACCEPTED AS AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-11 REPLACED CEDAR POST WITH A BERNTSEN AINB36 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO IDENTIFY THE CORNER POSITION.
SPRUCE 10" CEDAR 10" CEDAR 12" CEDAR 10" ALUMINUM SIGN POST
N67°E S55°E S54°W N42°W EAST
4.97' 52.19' 53.85' 21.20' 2.98' (TO FACE)
C-12 SET BERNTSEN AINB36 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO IDENTIFY THE CORNER POSITION.
CEDAR 12" W.BIRCH 4" CEDAR 9" W.BIRCH 6" ALUMINUM SIGN POST
N16°E N47°W S04°E S55°W EAST
39.17' 38.50' 41.82' 46.12' 2.85' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS NOTED OTHERWISE.

Signed by M.P. Davis Date 9/22/93

Surveyor's Michigan License No. 16926