

REMONUMENTATION

FEB 22 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On Sept 22, 1993

Robert E. Schmalzer Acting Chairman

For corners in DELTA (County)

Located In: Corner Code ##

- 1. Public Land Survey T 41 N R 18 W C-13
2. Property Controlling in Section S 32 T 41 N R 18 W 10
3. Miscellaneous Property in Sec. S T R

Recorded Oct 1, 1993 at 9:00 clock AM in Liber 7 Page 311 Walter C. Thum Reg. of Deeds Delta County, Michigan

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims SW COR SEC 32 & S. 1/16 COR W. LINE SEC 32

Grid table with columns A-M and rows 2-13. Cell 12,32 contains a dot.

I, M.P. DAVIS, in a field survey on AUGUST, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: C-13 [SW COR SEC 32] WOOD POST - JOHN BURT - 1845 (LYNN 6" N51'E 46 LINKS) (CEDAR 10" N38'W 25 LINKS) M.S. McNABB-DECEMBER 1919 - IDENTIFIED NW CORNER SEC 1 T40N R19W FROM GLO ET'S AND ESTABLISHED SW COR OF SEC 32 GLO DISTANCE EAST OF NW COR OF SEC 1. (BASSWOOD 6"-N32'W-3.0') (CEDAR STUMP-N46'E-20.0')

10 [S 1/16 ON W LINE SEC 32] NO RECORD EVIDENCE OF PREVIOUS ESTABLISHMENT OF THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: C-13 [SW COR SEC 32] NO EVIDENCE OF McNABB'S MONUMENT OR WITNESSES FOUND-RESET CORNER BY SURVEY LINE SOUTH FROM THE NW CORNER OF SEC 32 THRU THE W 1/4 COR AND ESTABLISHED CORNER AT PROPORTIONATE DISTANCE SOUTH OF 1/4 CORNER. THIS POSITION IS ACCEPTED AS A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

10 [S 1/16 ON W LINE OF SEC 32] ESTABLISHED CORNER POSITION AT THE MIDPOINT BETWEEN THE 1/4 CORNER TO THE NORTH & THE SEC CORNER TO THE SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-13 SET BERNTSEN A1NB36 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO IDENTIFY THE CORNER POSITION. ELM 6" N35'W 30.74' ELM 6" N82'E 38.10' ASH 5" S62'W 34.25' MAPLE 20" S08'E 84.42' ALUMINUM SIGN POST EAST 2.75'(TO FACE)
10 SET BERNTSEN A1NB36 ALUMINUM MONUMENT W/A 3-1/4" CAP STAMPED TO IDENTIFY THE CORNER POSITION. CEDAR 8" S56'W 19.28' CEDAR 6" S68'E 16.82' ALUMINUM SIGN POST EAST 2.90' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC - DISTANCES ARE TO A NAIL IN THE CENTER LINE OF THE OBJECT UNLESS NOTED OTHERWISE

Signed by M.P. DAVIS Date 9/22/93

Surveyor's Michigan License No. 16926