

SURVEY & REMONUMENTATION

JUL 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On May 5, 1998
Hubert R. Schmelzer
Chairman

For corners in

Delta
(County)

Located In:

Corner Code#

- 1. Public Land Survey T 41N R 18W K-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Recorded 13 May 1998
 at 9:00 o'clock AM in Liber 9 Page 80
Walter C. Thomas Reg. of Deeds.
 Delta County, Michigan
Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on February 25, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 K-8: Corner common to Sections 23 and 24
 1848: A. Merryweather original subdivision survey notes describe the corner monument as 1/4 post (no corner monument description given) referenced by:
 9" Cedar East 7 L 8" Cedar S 50°W 12 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 K-8:1998: No original corner evidence found. The corner was re-established equidistant and on line between the found Northwest corner and the re-established Southwest corner of Section 24. The distances North and South are 2635.26'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 K-8: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet marked Delta County Survey Monument stamped to identify the corner. Established references using painted blazes and dh nails in:
 8" Cedar N 73°W 7.43' 7" Cedar S 20°W 28.10'
 9" Cedar S 84°W 41.52' 10" Cedar N 51°W 18.46'

Green steel fence post w/ Yellow Survey Marker sign N 63°W 1.55'.

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Gerald W. Carlson Date 4-30-98

Surveyor's Michigan License No. 24589 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971