

SURVEY & REMONUMENTATION

JUL 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On May 5, 1998
Chas. R. Selmeier
Chairman

For corners in Delta (County) Located In: Corner Code #

1. Public Land Survey T 41N R 18W K-9
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Recorded 13 May 1998
at 9:00 o'clock AM in Liber 9 Page 81
Walter C. Thorne Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on February 25, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-9: Corner common to Sections 23, 24, 25 and 26.
1848: A. Merryweather original subdivision survey notes describe the corner monument as 1/4 post (no corner monument description given) referenced by:
4" Spruce S50°E 16 L 4" Spruce N 75°W 20 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-9:1998: No original corner evidence found. The North-South location of the corner was re-established equidistant between the found Northwest corner of Section 24 and the re-established Southwest corner of Section 25. The East-West location of the corner was proportioned between the "over creek" Call 23.59 chains West and the found Southeast corner of Section 24. The distances North and South are 5270.52' and the distance East is 5286.52'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet marked Delta County Survey Monument and stamped to identify the corner. Established references to painted blazes and dh nails in:
9" Cedar S 57°E 43.27' 9" Cedar S 02°E 28.79'
11" Cedar N 72°W 30.38' 8" Cedar N 14°W 56.64'

Green steel fence post w/ Yellow Survey Marker sign N 87°E 2.00'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 4-30-98

Surveyor's Michigan License No. 24589 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971