

SURVEY & REMONUMENTATION

JUL 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On May 5, 1998
Chut Schmelzing
Chairman

For corners in

Delta

Located In:

Corner Code #

(County)

- | | | |
|------------------------------------|---------------------------|-------------|
| 1. Public Land Survey | T <u>41N</u> R <u>18W</u> | <u>K-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Recorded 13 May 1998
at 9:00 clock AM in Liber 9 Page 83
Walter C. Thoman Reg. of Deeds.
Delta County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on February 23, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
K-11: Corner common to Sections 25, 26, 35 and 36
1848: A. Merryweather original subdivision survey notes describe the corner monument as 1/4 post (no corner monument description given) referenced by:
8: Spruce N 70°E 5 L 22" W. Pine S 70°W 17 L

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-11:1998: No original corner evidence found. The corner was re-established by surveying the centerline of the stream to the West and North of the corner. The centerline of the stream was plotted on transparent paper and a best fit of the stream Calls was used to re-establish the corner position. The streams Calls 1.70 chains West, 4.30 chains North and 6.20 chains North fit perfectly. The 3.25 chains North Call was about 10 feet short. The swamp edge West measured 490'(508.2' GLO) and swamp edge East measured 110' (132' GLO). The distance South is 5263.06, the distance East is 5212.80' and the distance North is 5270.52'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-11: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument stamped to identify the corner.
9" Cedar S 85°W 21.13' 21" W. Pine N 05°W 18.74'
5" Spruce N 54°E 29.46' 8" Cedar S 70°E 31.27'

Green steel fence post w/ Yellow Survey Marker sign N 67°W, 1.00'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 4-30-98

Surveyor's Michigan License No. 24589

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995