

JUL 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On May 5, 1998  
*Chris Schmeider*  
Chairman

For corners in Delta (County) Located In: Corner Code #

1. Public Land Survey T 41N R 18W K-12 *322*  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Recorded 13 May 1998  
 at 9:00 o'clock AM in Liber 9 Page 84  
*Walter C. Thorne* Reg. of Deeds.  
 Delta County, Michigan  
 Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on February 25, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-12: Quarter Corner common to Sections 35 and 36  
 1848: A. Merryweather original subdivision survey notes describe the corner monument as 1/4 post (no corner monument description given) referenced by:  
 8" Tamarack N 20°E 5 L 8" Cedar S 50°W 5 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12:1998: No original corner evidence found. The corner was re-established equidistant and on line between the re-established Northwest corner and the found Southwest corner of Section 36. The distances North and South are 2631.53'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument stamped to identify the corner. Established references using painted blazes and dh nails in:  
 5" Cedar N 32°W 9.73' 7" Cedar S 76°E 27.39'  
 4" Cedar S 42°E 41.45' 4" Cedar S 59°W 10.88'  
 Green steel fence post w/ Yellow Survey Marker sign N 05°E 2.64'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Gerald W. Carlson Date 4-30-98  
 Surveyor's Michigan License No. 24589