

**SURVEY & REMONUMENTATION**

**JUL 06 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On May 5, 1998  
*Robert A. Haveling*  
Chairman

For corners in

<u>Delta</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>41N</u> R <u>18W</u>	<u>L-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Recorded 13 May 1998  
9:00 o'clock AM in Liber 9 Page 85  
*William S. Thom* Reg. of Deeds  
Delta County, Michigan  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, GERALD W. CARLSON, in a field survey on February 25, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

L-9: South Quarter Corner Section 24  
1848: A. Merryweather's original Subdivision survey notes describe the corner monument as a 1/4 post (no corner monument description given) referenced by:  
7" Cedar            N 42°E    21 L            6" Balsam            S 34°W    12 L

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-9:1998: No original corner evidence found. The corner was re-established equidistant and on line between the re-established Southwest corner of Section 24 and the found Southeast corner of Section 24. The Distances East and West are 2643.26'.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-9: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument stamped to identify the corner. Monument is 0.3' above ground among balsams and scattered hardwoods. Established references using painted blazes and dh nails in:

8" Triple Maple    N 45°W    5.68'            7" Twin Maple    N 12°E    27.52'  
7" Maple            S 48°E    10.11'            8" Maple            S 15°W    31.68'  
Green steel fence post w/ Yellow Survey Marker sign S 76°W, 2.0'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 4-30-98

Surveyor's Michigan License No. 24589 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971