

SURVEY & REMONUMENTATION

JUL 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On May 5, 1998
Robert Blumeling
Chairman

For corners in Delta (County) Located In: Corner Code #

1. Public Land Survey	T <u>41N</u> R <u>18W</u>	<u>L-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Recorded 13 May 1998
8:00 o'clock AM in Liber 9 Page 86
Walter C. Thorne Reg. of Deeds.
Delta County, Michigan
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on February 27, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
L-11: South Quarter Corner Section 25
1848: A. Merryweather's original Subdivision survey notes describe the corner monument as a 1/4 post (no corner monument description given) referenced by:
20" Cedar N 10°W 12 L 18" Cedar S 30°E 11 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
L-11:1998: No original corner evidence found. The corner was re-established equidistant and on line between the re-established Southwest corner of Section 25 and the found Southeast corner of Section 25. The Distances East and West are 2606.40'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
L-11: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument stamped to identify the corner. Established references using painted blazes and dh nails in:
4" Balsam S 65°W 30.98' 4" Balsam N 38°W 26.13'
7" Spruce N 27°E 39.40' 3" Balsam S 42°E 33.83'
Green steel fence post w/ Yellow Survey Marker sign N 10°W, 1.75'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 4-30-98
Surveyor's Michigan License No. 24589

115