

SURVEY & REMONUMENTATION

JUL 06 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

9-75-76
 Approved By Delta County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On May 5, 1998
Robert Schmelzer
 Chairman

For corners in Delta (County) Located In: Corner Code #

1. Public Land Survey T 41N R 18W M-7
 T 41N R 18W K-13
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Recorded 13 May 1998
 at 9:00 o'clock AM in Liber 9 Page 75 & 76
Walter C. Thomas Reg. of Deeds.
 Delta County, Michigan
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, GERALD W. CARLSON, in a field survey on DECEMBER 5TH, 19 97, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 M-7: Corner common to Sections 13 and 24, T41N-R18W and Sections 18 and 19, T41N-R17W.

1845: John Burt's original Township survey notes describe the corner monument as a wood post referenced by:
 14" Sugar S 34°W 32L 18" Sugar N 75°W 35L
 (SEE REVERSE SIDE)

K-13: Corner common to Sections 35 and 36 on 4th Correction Line.

1845: John Burt's original Township survey notes describe the corner monument as a wood post referenced by:
 9" Cedar N 14°E 17L 6" Tamarack N 27°W 18L
 (SEE REVERSE SIDE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-7:1997: Found and accepted a 1988 Mead tablet stamped to identify corner. Found existing references as described in Part C below.

K-13: 1997: Found and accepted a 4" Michigan Department of Conservation Forest By Division Tablet stamped to identify the corner. Found existing references as described in Part C below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7: 1995: Found a 3 1/2" brass Mead tablet, 0.9' below road surface and stamped to identify location. Found witnesses with scribed blazes and dh nails in:

40" Hemlock N 50°W 87.26' 12" Cherry N 45°E 55.15'
 12" Maple S 20°E 58.10'

Established reference using face, butt and nail blaze in:

10" Cherry North 54.98'

K-13: 1995: Found a 1 1/2" O.D. pipe with a 4" brass DNR tablet stamped to identify the location 1.4' above ground in a Cedar swamp. Found witness trees have nails affixed. Blazes were not added as trees are in poor health.

8" Cedar N 23°W 28.26' 7" Cedar N 49°E 25.66'
 5" Cedar S 10°E 18.69' (Face and Butt Blaze)
 7" Cedar S 87°W 5.52' (Face and Butt Blaze)



Signed by Gerald W. Carlson Date 4-30-98
 Surveyor's Michigan License No. 24589

-7:

PART A CONTINUED:

988: An LCRC recorded by R.E. Schmeling RLS #8317, in L.6, RC Pg. 80-81, indicates that he found a 2" iron pipe several feet long bent and buried 2" under the sand road surface at the western terminal of Hass Road. He also checked a line call to Spring Brook SW at 30.50 chains (2013') and found it to measure 2028'. He replaced the bent pipe with a 1" diameter 4' long iron pipe with brass cap stamped with appropriate identification 12" below the road surface and along bent pipe left in place. Made new Bearing Trees marked with PK Nails and Scribing:

1" Hard Maple	S 18°E	58.2'	38" Hemlock	N 48°W	87.3'
1" Bl. Cherry	N 52°E	55.1'			

Set 6" Cedar Post with location tag, North 54.6'

13:

PART A CONTINUED:

962: An LCR recorded by B.D. Buckler in L. 3, RC Pg. 243, indicates that he reestablished the corner by single proportioned measurement. He also states that he set a 1" iron pipe with 4" brass cap and established the following references:

6" Cedar	N 45°E	38L	6" Cedar	N 29°W	42L
----------	--------	-----	----------	--------	-----