

**SURVEY & REMONUMENTATION**

**JUL 06 1998**

Approved By Delta County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On May 5, 1998

Robert K. ...  
Chairman

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**SECTION**

For corners in

Delta

(County)

Located In:

Corner Code #

1. Public Land Survey

T 41N R 18W

M-8

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling  
in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Recorded 13 May 1998

at 9:00 o'clock AM in Liber 9 Page 77

William C. Thorne Reg. of Deeds.  
Delta County, Michigan

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on February 24, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

**M-8: East Quarter corner Section 24**

1845: John Burt's original survey notes describe the corner monument as a set 1/4 Section post (no corner monument description given) referenced by:

5: Hemlock S 57°W 42 L 7" Hemlock N 80°W 38 L

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**M-8:1998:** No original corner evidence found. The corner was re-established equidistant and on line between the found Northeast and Southeast corners of Section 24. The distances North and South are 2658.60'. A Tom O'Brien 1/2" iron w/cap No. 21274 was found 6.60' Southwest of this position and upon consultation with Tom it was determined this 1/2" iron was set in the wrong position and was pulled out per Tom's concurrence.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**M-8: 1998:** Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet Delta County Survey Monument stamped to identify the corner. Established references with painted blazes and dh nails in:

- 12" Maple N 48°E 19.00' (O'Brien NBT)
- 8" Cedar S 51°E 53.80' (O'Brien NBT)
- 14" Maple S 42°W 80.65' (O'Brien NBT)
- 8" Maple S 78°W 27.46'

Green steel fence post w/ Yellow Survey Marker sign N 74°E, 1.54'

Centerline North-South road West, 20.25'

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.

LIBER **0009** PAGE **077**



Signed by Gerald W. Carlson Date 4-30-98

Surveyor's Michigan License No. 24589 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995