

SURVEY & REMONUMENTATION

JUL 06 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved By Delta County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On May 5, 1998
Robert A. Cusling
 Chairman

SECTION

For corners in

Delta
 (County)

Located In:

Corner Code #

- | | | | |
|------------------------------------|---------|--------------------|-------------|
| 1. Public Land Survey | | <u>T 41N R 18W</u> | <u>M-10</u> |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| | | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ R _____ | _____ |
| | S _____ | T _____ R _____ | _____ |

Recorded 13 May 1998
 at 9:00 o'clock AM in Liber 9 Page 78
William C. Thomas Reg. of Deeds.
 Delta County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, GERALD W. CARLSON, in a field survey on February 25, 19 98, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-10: East Quarter Corner of Section 25

1845: John Burt's original Township survey notes describe the corner monument as a 1/4 section post (no corner monument description given) referenced by:
 16" Cedar S 34°W 27 L 10" Cedar N 21°W 14 L

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10:1998: No original corner evidence found. The corner was reestablished equidistant and on line between the found Northeast and Southeast corners of Section 25. The distances North and South are 2659.82'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10: 1998: Set a 2 3/8" O.D. aluminum pipe capped with a 3 1/4" diameter aluminum tablet, encased in concrete, marked Delta County Survey Monument stamped to identify the corner. Established references using painted blazes and dh nails in:

- | | | | | | |
|---|--------|--------|-----------|--------|--------|
| 4" Balsam | N 18°W | 27.12' | 4" Balsam | S 75°E | 66.40' |
| 4" Balsam | S 17°E | 49.55' | 5" Balsam | S 06°W | 25.20' |
| Green steel fence post w/ Yellow Survey Marker sign N 70°W, 2.00' | | | | | |

Note: Bearing trees have painted face, butt, and side nail blazes, d.h. measuring nails, and stamped B.T. Tags affixed.



Signed by Gerald W. Carlson Date 4-30-98
 Surveyor's Michigan License No. 24589