

**SURVEY & REMONUMENTATION**

NOV 25 1998

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Fixing Requirement of Act 74, Mich. P.A. 1970**

Approved By Delta County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On June 26, 1998  
*Robert Schmelzer*  
 Acting Chairman

For corners in  
DELTA  
 (County)

Located In: Corner Code #

1. Public Land Survey	T	41	N	22	W	<u>B-05 &amp; B-07</u>
	T		R			
	T		R			
	T		R			
2. Property Controlling in Section	S		T		R	
	S		T		R	
3. Miscellaneous Property in Sec.	S		T		R	
	S		T		R	

Recorded July 7 1998  
 at 9:00 o'clock AM  
 Lib. 9 Page 89  
*Walter C. Thorne*  
 Delta County Reg. & Deeds

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims B-05 [N1/4 SEC 18] B-07 [N1/4 SEC 19]

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on JULY 1 & 6, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 B-05 [N1/4 COR SEC 18] A.MERRYWEATHER, DS - 1847 - WOOD POST - (CEDAR 08°-N42°E-18 LINKS)(W.PINE 12°-S65°W-50 LINKS)  
 M.S.McNABB-1922-ID CORNER POSITION FROM "GLO" W.PINE BT SW, NOW A STUMP - SET NEW STAKE & NOTED NEW CEDAR BT 8' N75°W 27.25'  
 B-07 [N1/4 COR SEC 19] A.MERRYWEATHER, DS - 1847 - WOOD POST - (BURNT TAMARACK 09°-N12°W-16 LINKS)(BIRCH 07°-S10°E-12 LINKS)  
 M.S.McNABB-1927-FOUND STAKE IN PLACE & BT STAKE S80°W 30'-SET NEW STAKES WITH STONES AROUND NORTH SIDE & SET BT STAKES NW & SW 33'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 B-05 [N1/4 COR SEC 18] FOUND IN PLACE, 6"± BELOW GRADE, A POST POINT. ID THE SAME AS BEING THE SAME CORNER AS FOUND IN 1922 BY M.S.McNABB. STUMP OF "GLO" W.PINE BT SW WITH MEASURING NOTCH PLAIN & STUMP OF McNABB'S CEDAR BT NW STILL IN PLACE. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFULL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.  
 B-07 [N1/4 COR SEC 19] FOUND IN PLACE REMAINS OF SQUARED WOOD POST WITH STONES SET AROUND THE NORTH SIDE. NO EVIDENCE OF McNABB'S BT STAKES TO BE FOUND. CORNER POSITION CHECKS WELL WITH THE "GLO" CALL WEST TO THE DAYS RIVER AND WITH OTHER SUREVEY MONUMENTS FOUND OF McNABB'S 1927 SURVEY OF THE NORTH-SOUTH 1/4 LINE OF SEC 19. ACCEPTED EXISTING CORNER AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 B-05 REPLACE EXISTING MONUMENT W/A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE COR POSITION.  
 CEDAR 09" CEDAR 05" ASH 08" CEDAR 06" SURVEY MONUMENT SIGN POST  
 N63°W N65°E S45°E S49°E NORTH  
 37.59' 10.56' 45.50' 31.52' 2.24' (TO FACE)  
 B-07 REPLACED EXISTING MONUMENT W/A A BERNTSEN A1NB30 ALUM MONUMENT WITH THE CAP STAMPED TO ID THE CORNER POSITION.  
 BALSAM 07" BALSAM 09" BALSAM 12" SURVEY MONUMENT SIGN POST  
 N75°W S30°E S25°W N45°E  
 16.92' 49.00' 22.93' 1.60' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 7/7/98  
 Surveyor's Michigan License No. 16926