

LAND CORNER RECORDATION CERTIFICATE
DELTA Co. FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY-----	T. <u>41N</u> N. S., R. <u>22W</u> E. W.	<u>I-5, J-5, K-6</u>
2. PROPERTY CONTROLLING IN SECTION-----	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION-----	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-8, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-5 - N.W. Sec. Cor. of Sec. 14; wood post - Birch 12" - N35°E - 22 Lks.; Hemlock 12" - S25°W - 17 Lks.
- J-5 - North 1/4 Cor. of Sec. 14; wood post - Birch 7" - N30°E - 8 Lks.; Birch 10" - S10°W - 14 Lks.
- K-6 - East 1/4 Cor. of Sec. 14; wood post - W. Maple 6" - S38°E - 22 Lks.; Balsam 8" - N30°W - 8 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-5 - Set in center line of E-W road in line with old fence line South. Measurements N-S-E & W to known corners are reasonable.
- J-5 - Set M.P.O.L. between the N.E. & N.W. Sec. Cors. of Sec. 14.
- K-6 - Set M.P.O.L. between the N.E. and S.E. Sec. Cors. of Sec. 14. This area has been bulldozed and all old marks destroyed.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-5 - 1" pipe, 4" aluminum cap; 5" Balsam - N25°W - 84.0'; 8" W. Birch - N49°E - 58.9'; 3" R. Maple - S64°E - 50.2'; 7" W. Spruce - S50°W - 58.6'.
- J-5 - 1" pipe, 4" aluminum cap; 8" R. Maple - N24°W - 19.6'; 7" B. spruce - N49°E - 35.1'; 10" R. Maple - N76°E - 8.9'; 6" B. Spruce - S35°W - 40.9'.
- K-6 - 1" pipe, 4" aluminum cap; 7" R. Maple - N47°W - 23.85'; 13" R. Pine - N68°W - 90.50'; 5" Balsam Fir - S59°W - 53.00'; 3" Red Pine - N14°W - 51.80'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: