

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____ N. S. R. _____ E. W.		
2. PROPERTY CONTROLLING IN SECTION <u>14</u> T. <u>41N</u> N. S. R. <u>22W</u> E. W.		<u>14, 1</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S. R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

David B. Babbitt

I, _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-8- 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 14 - South 1/16 Cor. on the East Sec. line of Sec. 14; not previously established.
- 1 - West 1/16 Cor. on the North Sec. line of Sec. 14; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 14 - Set M.P.O.L. between the East 1/4 Cor. and the S.E. Sec. Cor. of Sec. 14.
- 1 - Set M.P.O.L. between the North 1/4 Cor. and the N.W. Sec. Cor. of Sec. 14.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 14 - D.N.R. Monument; 5" Cedar - S87°W - 21.1'; 10" Cedar - N60°W - 36.9'; 7" Balsam - N28°E - 19.95'; 11" Spruce - S23°E - 12.05'; right bank of Tacoosh River - North - 22'.
- 1 - D.N.R. Monument; 4" Balsam Fir - S42°E - 27.4'; 5" R. Pine - S53°W - 70.2'; 10" R. Pine - S84°W - 60.5'; 4" R. Maple - N22°E - 31.9'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)