

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41N N. S., R. 22W E. W.	K-9
2. PROPERTY CONTROLL- ING IN SECTION _____ 26	, T. 41N N. S., R. 22W E. W.	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____	, RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 5, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-9 - N.E. Sec. Cor. of Sec. 26; Marcus McNabb-1914 set and marked stake - Pine stump - S. 27 Ft.; Nor. Pine 14 - N75W - 36 Ft.

7 - N 1/16 Cor. on the East Sec. Line of Sec. 26; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-9 - Set by retracing the survey tie shown on the R.O.W. plans (21-R-1) for Hwy. M-186. Apparent date 1933. This position is verified by Marcus McNabb survey record for the North Sec. line of Sec. 26 dated September 1914. McNabb's N.B.T.'s apparently destroyed by road construction.

7 - Set M.P.O.L. between the N.E. Sec. Cor. and the East 1/4 Cor. of Sec. 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 - 1" pipe, 4" aluminum cap; 14" R. Pine - S44°E - 122.2'; 12" R. Pine - S15°W - 47.2';
14" R. Pine - S42°W - 105.7'; 3" Oak - N5°E - 37.8'.

7 1" pipe, 4" aluminum cap; 5" W. Pine - N44°E - 32.1'; 8" R. Pine - S46°E - 48.2';
7" R. Maple - S20°E - 84.4'; 10" R. Pine - S29°W - 50.1'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: