

DELTA**LAND CORNER RECORDATION CERTIFICATE****FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41N N. S., R. 22W E. W.	I-4, K-7
2. PROPERTY CONTROLLING IN SECTION - 23	T. 41N N. S., R. 22W E. W.	14
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 7-8, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 - West 1/4 Cor. of Sec. 11; wood post - Cedar 6" - N80°E - 14 Lks; B. Ash 5" - N64°W - 22 Lks.
 K-7 - N.E. Sec. Cor. of Sec. 23; Marcus McNabb 1919 set & marked stake (no N.B.T.'s noted).
 14 - South 1/16 - East boundary Section 23; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-4 - Found old Sq. Cedar post and the point of another. There is a Cedar Stp. in the proper position for the N.E. O.B.T. but mostly rotted away. Too far gone to see any marks. Distances North & South look good. Set D.N.R. Mon. at old posts.
 K-7 - Found very old Sq. Cedar Post. Replaced with D.N.R. Mon.
 14 - Set M.P.O.L. between the E 1/4 Cor. and the S.E. Sec. Cor. of Sec. 23.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-4 - D.N.R. Monument; 9" Cedar - S20°W - 22.25'; 10" Cedar - N55°W - 9.5'; 6" Cedar - N26°E - 15.0'; 7" Cedar - S72°E - 7.2'.
 K-7 - D.N.R. Monument; 4" Maple (in clump) - S70°W - 23.55'; 11" R. Pine - S12°W - 35.6'; 6" W. Pine - S55°E - 67.9'; 6" Maple - N10°E - 22.9'.
 14 - D.N.R. Monument; Cor. is buried in approximate center line of dirt road; 10" Red Pine - N76°E - 72.0'; 4" Red Pine - S21°E - 38.2'; 6" R. Pine - S79°W - 31.6'; 5" R. Pine - N54°W - 30.1'.

SIGNED BY

David B. Babbitt

DATE

9-15-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)