

* Delta Co.

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>6</u> T. <u>41</u> N. S., R. <u>22</u> E. W.		<u>A-2</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on July 26 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

West 1/4 corner. M. McNabb 1915; ID. by stake and B.T.; Cedar tree 9" - N10°E - 15' set previously.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

This corner was previously set, supposedly on line across the center and E 1/4 corner of Sec. 6, T41N-R23W as indicated in an old survey by M. McNabb in 1915 and on line between the NE & SE section corners on Section 1.

Because of an error in our field notes it was set in the wrong position. Also because of said error an old square cedar post previously ignored because it seemed to be too far out of position and had no supporting evidence now appears reasonable although it is somewhat west of a straight line between the NE & SE section corners and is south of a straight line across the cabin spike found at (or near) the center of Sec. 6 and the E 1/4 corner of Sec. 6. It is not so far off as to be unreasonable for either and the spike at the center of Sec. 6 may not be (See Reverse Side)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe, 4" aluminum cap; 7" Tamarack - N80°E - 3.8'; 5" Cedar - S51°E - 17.0'; 5" Cedar - S25°E - 23.9'; 5" Cedar - N43°W - 15.75'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 10-10-79
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558