

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>41</u> ^N / _S , R. <u>22</u> ^E / _W .		<u>A-2, C-2</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA
CO.

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 22 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

A-2 - M. McNabb, 1915 id. by stake and bearing cedar tree 9" N10°E - 15 feet. Set in previous survey.
 C-2 M. McNabb, 1915 iron rail in place set previous B.T. TAM. 7" southeasterly 21.4 feet.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-2 - No old survey marks found. Set on line between sec. cors. ½ mile north and ½ mile south and in line with the ctr. post and east ¼ cor. of Sec. 6 as recorded by M. McNabb in 1915
 C-2 Found section of railroad rail in south slope of road fill (M-35) and in line with old fence line south. B.T. would fall in cleared roadway.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2 1" pipe, 4" aluminum cap
 6" cedar - N44°E - 19.2'
 6" cedar - N76°E - 10.6'
 8" tamarack - N12°E - 25.2'
 C-2 1" pipe, 4" aluminum cap
 8" cedar - S3°E - 66.5'
 3" cedar - S29°W - 59.6'
 Center of hwy. R.O.W. Mon. S63°E - 91.3'
 Centerline highway M-35 - north - 36.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR