

DELTA

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

P.R.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41 N. R. 22 W.	G-11, G-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 20 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- G-11 N.W. Section corner - Section 34; Wood Post, H. Maple 10" - N62°W - 46 lks.; Hemlock 12" - N5°E - 32 lks.
- G-12 West 1/4 corner - Section 34; Wood Post, N. Pine 12" - S30°W - 35 lks.; N. Pine 16" - N50°E - 45 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- G-11 Set D.N.R. monument in place of 1-1/2" pipe as indicated by a USFS location poster on a cedar post nearby. This pipe was also used as the section corner by Davis Surveying of Escanaba in early April 1981. No sign of O.B.T.'s.
- G-12 Set M.P.O.L. between the N.W. and S.W. section corners of Sec. 34. Fits swamp calls from the south at 26.50 and 36.00 very well. No sign of O.B.T.'s - corner falls in pine plantation about 50' from the west edge of the plantation.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- ALL 1" pipe, 4" aluminum cap.
- G-11 8" W. Birch - S81°W - 19.8'; 3" W. Pine - N1°W - 12.8'; 7" R. Maple - N69°E - 5.9'; 7" W. Birch - S39°E - 8.3'; Location Post - N45°W - 7.26'.
- G-12 6" R. Pine - N10°E - 5.80'; 7" R. Pine - N87°W - 4.55'; 7" R. Pine - N61°E - 27.80'; 9" R. Pine - S75°E - 19.50'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-13-81  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558