

DELTA

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>41</u> N. S., R. <u>22</u> E. W.	<u>10, 13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 21, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 10 South 1/16 corner on the West section line of Section 34; not previously established.
- 13 Southeast 1/16 - Section 34; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 10 Set M.P.O.L. between the West 1/4 corner and the S.W. section corner of Section 34.
- 13 Set at the computed center of the S.E. 1/4 of Section 34 by closed traverse.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL 1" pipe, 4" aluminum cap.
- 10 9" R. Pine - N4°E - 62.3'; 9" R. Pine - N39°E - 43.85'; 9" R. Pine - S30°E - 81.9'; 6" J. Pine - S65°W - 49.5'.
 - 13 9" Aspen - S71°E - 20.35'; 8" R. Pine - S5°W - 27.00'; 7" R. Pine - S40°W - 13.65'; 8" R. Pine - N74°W - 12.80'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt DATE 7-13-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558