

DELTA

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--                           | LOCATED IN--                   | CORNER CODE NUMBER |
|--|--------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. 41 N. S., R. 22 E. W.       | K-11, L-11         |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. _____ N. S., R. _____ E. W. | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____      |                                |                    |
| 5. PRIVATE CLAIMS _____                    |                                |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 1 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-11 N.W. section corner of Section 36; Wood Post, Tam. 5" - N18°W - 7 lks.; Cedar 6" - S65°E - 4 lks.
- L-11 North 1/4 corner of Section 36; McNabb - 1917; Wood Post; W. Birch 5" - N78°E - 21'; W. Birch 6" - S30°E - 27.3'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-11 Set by prop. to G.L.O. measuring east and west, using the north 1/4 corner of Sec. 36 and the N.W. section corner of Sec. 35, and in the centerline of road east. Local land owner, R. Stemas, says he saw the cedar stub of an O.B.T. being buried in the road fill at the time of US-2 & 41 relocation. Said stub was also mentioned in USFS notes dated 1937. Distance to high bluff 9 chs. west as recorded in USFS record is also good.
- L-11 Set in front of USFS corner tag on cedar tree and on the north edge of fill on E-W road. This position fits occupation lines east and south and the mea. south to the occupied center of Sec. 36 fits Marcus McNabb's survey record of 1917. No sign of McNabb's N.B.T.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL 1" pipe, 4" aluminum cap.
- K-11 9" Cedar - N14°E - 67.7'; 8" B. Spruce - N39°E - 65.1'; 7" Cedar - S53°W - 94.9'; 4" Cedar - S16°E - 69.6'.
- L-11 5" Cedar - N70°E - 41.9'; 5" Cedar - N08°E - 53.1'; 6" Cedar - N59°W - 28.1'; 6" Cedar - South - 88.35'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 7-13-81 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558