

DELTA

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41</u> N. <u>22</u> R. <u>22</u> W.	<u>G-13, I-11, I-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on April 10 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-13** S.W. corner of Section 34; Wood Post, W. Pine 24" - N40°E - 45 lks.; Balsam 6" - N55°W - 19 lks.
- I-11** N.E. section corner - Section 34; Wood Post, Balsam 4" - N48°E - 17 lks.; Balsam 4" - S80°W - 12 lks. USFS recrods of 1937 note a cedar post for this corner - no N.B.T.'s.
- I-12** East 1/4 corner - Section 34; Wood Post, Birch 10" - South - 12 lks.; Birch 6" - N10°W - 8 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-13** Set from old USFS cedar post at fence corner; fence North & west. Not of record but fits surrounding corners well. N.B.T.'s by M.D.S.H. in place and used by Davis Surveying of Escanaba, also. No sign of O.B.T.'s.
- I-11** Set from old U.S. Forest Service post. Noted as cedar post in USFS records of 1937. No sign of original evidence at this time. Corner is near the double prop. position.
- I-12** Set M.P.O.L. between the N.E. & S.E. section corners of Section 34. No sign of O.B.T.'s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL** 1" pipe, 4" aluminum cap.
- G-13** 20" W. Pine - N5°W - 60.4'; 9" W. Pine - N82°E - 45.8'; 9" W. Birch - S54°E - 35.2'; 4" W. Pine - S11°W - 21.3'.
- I-11** 9" Triple W. Birch - N7°W - 28.8'; 8" B. Spruce - S32°W - 27.0'; 9" B. Spruce - S20°E - 12.9'; 3" Twin B. Spruce - N59°E - 16.9'.
- I-12** 7" Tamarack - N63°W - 17.40'; 9" Tamarack - South - 26.15'; 15" R. Pine - N4°E - 54.00'; 6" B. Spruce - N70°E - 9.60'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 7-13-81  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558