

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA CO.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 41 N. R. 22 W.	J-10, K-10
2. PROPERTY CONTROLLING IN SECTION 26	T. 41 N. R. 22 W.	8
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 0 Center 1/4 corner of Section 26; not previously established.
- 0 East 1/4 corner of Section 26; wood post N. Pine 8" - N20°E - 13 lks. Birch 10" - S30°W - 21 lks.
West 1/16 corner on the E-W 1/4 line of Section 26; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 0 Set at the intersection of the N-S and E-W 1/4 lines of Section 26.
- 0 Found 1 1/2" pipe not of record but it is reasonable in relation to other corner Mons. in the area. Replaced pipe with DNR Mon.

Set M.P.O.L. between the center of section and the W. 1/4 corner of Section 26. Falls about 30' up from the bottom of a high steep bank west of the Days River.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 0 D.N.R. Mon.; 9" R. Pine - N23°W-51.7; 6" R. Pine - N40°W-40.7; 9" W. Pine - S60°E-34.7; 7" R. Pine - S23°W-67.0'.
- 0 1" pipe, 4" aluminum cap; 3" Balsam - S3°E - 24.9'; 9" R. Maple - N16°E - 27.6'; 7" R. Maple - N71°E - 65.3'; 10" R. Maple - S44°E - 45.3'.

D.N.R. Mon.; 10" Spruce - N22°W-25.2'; 7" Hem. - N30°W-12.9'; 12" R. Pine - S85°W - 3.5'; 9" Spruce - S35°W-5.1'.

SIGNED BY

David B. Babbitt

DATE 12-22-1981