

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA CO.

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---------------|--------------------|
| 1. PUBLIC LAND SURVEY _____ T. _____ N. _____ E. _____ S., R. _____ W. _____ | | |
| 2. PROPERTY CONTROLLING IN SECTION <u>25</u> , T. <u>41</u> , N. <u>22</u> , E. <u>10, 15</u> S., R. <u>22</u> W. _____ | | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. _____ E. _____ S., R. _____ W. _____ | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

South 1/16 corner on the West Section line of Section 25; not previously established.

West 1/16 corner on the South Section line of Section 25; the plats of "Bay de Noc Addition to Masonville" dated 1888 and the "Bay View Addition to North Gladstone" dated 1890 both show this corner as one corner of the plat; however, these plats were never developed and there is no sign that they were ever monumented on the ground. Mea. E-W on these plats differ by 4 feet per 1/4 mile from the measurements on the W. 1/2 of the S. Section line of Section 25 in our present survey.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Set M.P.O.L. between the W. 1/4 corner and the S.W. section corner of Section 25.

Set M.P.O.L. between the S. 1/4 corner and the S.W. section corner of Section 25.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I 1" pipe, 4" aluminum cap

5" Cedar - S19°E - 19.0'; 9" Cedar - S29°W - 14.95'; 4" Cedar - S86°E - 11.35';
4" Cedar - N82°W - 2.8'.

4" Cedar - S63°E - 113.7'; 5" Cedar - S47°E - 43.25'; 4" Cedar - S09°W - 31.0';
5" Cedar - S53°W - 47.25'.

SIGNED BY

David B. Babbitt

DATE 12-22-81