

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*DELTA*

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____ T. 41 N. S., R. 22 E. W.		K-5 & K-3
2. PROPERTY CONTROLL- 11 ING IN SECTION_____ , T. 41 N. S., R. 22 E. W.		7
3. MISCELLANEOUS PROPERTY IN SECTION_____ , T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 12, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- K-3 - NE sec. corner of Section 11; by M. McNabb-1917; I.D. by orig. Birch B.T. plain; B.T. stake N45°E - 33 ft; Cedar 10 - S13°E - 17 ft.
- K-5 - S.E. corner of Section 11; wood post - N. Pine 18" - S30°E - 22 lks; Balsam 8" N35°W - 33 lks.
- 7 - N 1/16 corner on East boundary Section 11; By McNabb - 1917 set 1/8 corner. B.T.s - W. Birch 15" - N53°W - 23.6 ft; Soft Maple 9" - S50°E - 3.3 ft.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- K-3 - Found point of old wood post (presumably set by M. McNabb in 1917) in line with centerline of roads in N. & E. and old fence lines W.&S. McNabb's N.B.T.s apparently destroyed by rd. construction.
- K-5 - Set from stump of 18" N. Pine-S30°E-22 lks. Now 20" in diameter. Stump is burned but has definite partial hack mark under strip of overgrowth.
- 7 - Set M.P.O.L. between the N.E. section corner and the E. 1/4 corner of Section 11. No sign of McNabb's B.T.s.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- K-3 - 1" pipe, 4" aluminum cap; 14" W. Spruce - N39°W - 39.4'; 6" Balsam - N89°W - 22.4'; power pole - S12°W - 75.5'; 9" Balsam - S32°E - 47.0'.
- K-5 - 1" pipe, 4" aluminum cap; 10" B. Spruce - N74°E - 24.7'; 5" B. Spruce - S69°W - 20.0'; 6" B. Spruce - S54°E - 31.4'; 9" B. Spruce - N50°W - 0.6'.
- 7 - 1" pipe, 4" aluminum cap; 9" Balsam Fir - N87°E - 1.7'; 10" W. Spruce - S79°E - 20.8'; 5" W. Birch - S7°W - 6.9'; 4" Balsam Fir - S84°W - 17.8'.

SIGNED BY

*David B. Babbitt*

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: