

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DELTA

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>41</u> N. S., R. <u>22</u> E. W.	<u>K-4</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 12, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

K-4 - East 1/4 corner of Section 11; M. McNabb - 1917 - established on old line correct BT (Poplar 3-N40°E - 16.5'; Poplar 2-South-17'.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-4 - Set on line between the N.E. & S.E. sec. corners of Section 11, but not at mid-point. Notes of the original Gov't survey indicate that this corner was set 15 lks. south of a creek and mid-point would fall on high ground North of the creek. This corner was, therefore, set at 2693.7 ft. from the N.E. Section corner and 2653.87 ft. from the S.E. sec. corner. This still places the corner North of the present creek position but it is 15 lks. South of an older creek channel and is at the most northerly position possible to fit the original survey record. M. McNabb shows a measurement of 2688.8 ft. for the North 1/2 of this section line in 1917 but he did not measure the South 1/2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 - 1" pipe, 4" aluminum cap; 6" Twin Red Maple - N67°W - 23.8'; 16" W. Birch - N35°W - 23.3'; 9" R. Maple - N34°E - 33.9'; 6" Balsam - S06°E - 55.6'.

SIGNED BY

David B. Babbitt

DATE

8-12-82

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)