

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

DELTA CO.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41N</u> N. S., R. <u>22W</u> E. W.	<u>L-5, M-5, L-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on January 26, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-5 - N 1/4 Cor. of Sec. 13; wood post - Birch 4" - N70°W - 10 Lks; Hemlock - East - 28 Lks. (Hemlock size not given).
- M-5 - Northeast Corner Section 13; Marcus McNabb - 1914. Remains of Orig. Tam. B.T. Re-set stake - B.T. stake N.W. & S.E. Mag. C.
- L-7 - S 1/4 Cor. of Sec. 13; wood post - Hemlock 8" - S3°E - 7 Lks; Cedar 12" - N10°W - 11 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-5 - Set M.P.O.L. between the N.W. and N.E. Sec. Cors. of Sec. 13. No sign of O.B.T.s.
- M-5 - Found Sq. Cedar post. Mea. South for a mile agrees with McNabbs 1914 survey record. Replaced post with D.N.R. Mon.
- L-7 - Set M.P.O.L. between the S.E. & S.W. Sec. Cors. of Sec. 13. Falls in a narrow neck of swamp - no sign of O.B.T.s.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-5 - D.N.R. Mon.; 9" Cedar - S26°W - 34.8'; 3" Cedar - South - 18.4'; 5" Cedar - S36°W - 12.7'; 3" Cedar - N48°W - 10.7'.
- M-5 - D.N.R. Mon.; 7" Cedar - S65°W - 27.5'; 7" Cedar S1°E - 21.7'; 4" B. Spruce - N84°W - 21.4'; 8" Balsam Fir - N1°W - 37.0'.
- L-7 - D.N.R. Mon.; 24" W. Pine - N3°E - 72.2'; 4" R. Maple - S60°E - 20.1'; 7" Balsam Fir - S18°E - 10.9'; 9" R. Maple - N40°W - 29.8'.

SIGNED BY

*David B. Babbitt*

DATE

3-7-83

SURVEYOR'S MICHIGAN REGISTRATION NO.

21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: