

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 41N N. S., R. 22W E. W.	L-9, L-8
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 28, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

L-9 South 1/4 Cor. of Sec. 24.	L-8 C1/4 Sec. 24
Wood post	Not prev. est.
Cedar 7" - North - 8 Lks.	
Balsam 8" - N2E - 16 Lks.	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

L-9 Set M.P.O.L. between the S.W. and S.E. Sec. Cors. of Sec. 24.

L-8 Set at the intersection of the N-S and E-W 1/4 lines of Sec. 24.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 1" pipe 4" alum cap	L-8 1" pipe 4" alum. cap
9" cedar S11°E 8.1'	18" red pine N64°E 26.3'
4" cedar N6°E 16.1'	4" red pine S58°E 34.9'
5" cedar N54°W 23.4'	6" red pine N85°W 39.0'
6" cedar S37°W 9.8'	3" w. pine S47°W 13.4'

SIGNED BY \_\_\_\_\_

David B. Babbitt

DATE \_\_\_\_\_

9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)