

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>41N</u> N. S., R. <u>22W</u> E. W.	<u>M-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

David B. Babbitt

I, _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 29, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

SE Sec. Cor. of Sec. 24	Marcus McNabb Record	Mel Davis, RLS Liber 4-Pg. 200
Orig. Govt. Survey	Set iron pipe	Found 1/2" iron in blacktop rd.
Wood post	BTs W. pine 8"-N35E-32.4'	E tele. pole #19, N32°W-41.8'
W. pine 8"-N32W-12 Lks.	N. pine S50W-24.6'	E tele. pole #18, N60°E-65.2'
W. pine 10"-S43W-22 Lks.		E elec. pole #107-S6°W-47.7'
	MDOT plans 21-R-1 Sheet 59	
	Appr. Date 1933, show this	
	Sec. Cor. 10.6' north of E of	
	M-86 (now a county road).	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

This section corner was re-established at 10.6' north of the centerline of Old M-86, (now a county road) as indicated on MDOT plans (21-R-1) and in line with the E of a graded road north (directly north of an existing 1/2" iron in a mon. box in the E of Old M-86. Measurements east and west agree with the stationing shown on MDOT plans (21-R-1) and the measurement north to the east 1/4 cor. of Sec. 24 agrees reasonably well with Marcus McNabb's recorded measurement. The location of this corner and the existence of the MDOT plans showing said location were brought to my attention by Mel Davis, RLS. Mel Davis stated to me that the "1/2" iron in blacktop road" which he found and which is recorded in Liber 4 - page 200 is not the true section corner location and that the corner belongs 10.6' north of the road as shown.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: -over-

1" pipe 4" alum. cap.
Power pole (pk) S6°W 58.3'
Pipeline marker S36°W 47.6'
12" red pine N44°W 41.2'
19" w. pine N76°E 69.0'

Iron rod in monument box E road, south - 10.6'

SIGNED BY _____

David B. Babbitt

DATE _____

9-12-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES.