

SURVEY & REMONUMENTATION

SEP 18 1997

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On July 23, 1992

Robert Schulz
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code ##

28 July 1997

at 9:00 o'clock a.m.

Day 8 Page 212

William C. Thum
Delta County, Ill. Reg. of Deeds

Register of Deeds Stamp & File Number

- | | | | |
|---------------------------------------|--|-------------|--|
| 1. Public Land Survey | T <u>41 N</u> R <u>23 W</u> | C-11 & C-12 | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| | T _____ R _____ | | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | | |
| | S _____ T _____ R _____ | | |
| 4. Lot No. _____, Recorded Plat _____ | | | |
| 5. Private Claims | C-11 NW COR SEC 32 C-12 W1/4 COR SEC 32 | | |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, M.P. DAVIS, in a field survey on 16 JUNE/11 FEBRUARY, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- C-11 [NW COR SEC 32]- A.MERRYWEATHER, D.S.-1847-WOOD POST (CEDAR 12"-N26°E-34 LINKS)(BIRCH 16"-S40°W-20 LINKS)
M.S.McNABB-1918-IRON PIPE & STAKE -ID FROM ORIGINALS-SET BT STAKES NW & SE 33'
M.S.McNABB-1947-FROM PREVIOUS SURVEY-FENCE LINES WEST & SOUTH CORNER FENCE POST WEST 4.5'

 - C-12 [W1/4 COR SEC 32] A.MERRYWEATHER, D.S.-1847-WOOD POST (BIRCH 18"-EAST -19 LINKS)(BIRCH 10"-WEST -30 LINKS)
M.S.McNABB-1918-FOUND IN PLACE IRON GAS PIPE & BT STAKE NW 33'-NEW BT'S N. GATE POST N80°E-19.5' & COR FENCE POST S30°E-38.4'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- C-11 [NW COR SEC 32] FOUND IN PLACE 1" IRON PIPE 4.5' EAST OF REMAINS OF OLD CORNER FENCE POST. NO EVIDENCE OF McNABB'S BT STAKES. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

 - C-12 [W1/4 COR SEC 32] FOUND IN PLACE 1" IRON PIPE. ID SAME FROM COMPARISON OF McNABB'S DISTANCE TO ADJOINING CORNERS WHICH CHECK WELL. ACCEPTED EXISTING MONUMENT AS THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- C-11 REPLACED EXISTING MONUMENT A BERNTSEN ALNB30 ALUM MON W/A 3 1/4" CAP STAMPED TO ID THE CORNER POSITION

MAPLE 8"	SPRUCE 6"	SPRUCE 5"	SURVEY MONUMENT SIGN POST
NORTH	S78°E	S8°W	WEST
7.38'	6.53'	13.52'	2.24' (TO FACE)

 - C-12 REPLACED EXISTING MON W/A 4"X4"X36" CONC MON W/A 3" BRASS CAP STAMPED TO ID THE CORNER POSITION.

SPRUCE 4"	TAMARACK 5"	POWER POLE	SURVEY MONUMENT SIGN POST	C/L COUNTY RD. 523
N30°W	N48°E	S40°W	EAST	WEST
33.12'	40.58'	42.61'	1.55' (TO FACE)	

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 7/23/97
Surveyor's Michigan License No. 16926