

OCT 31 1997

COMMISSION

Approved By Delta County Land Survey Remonumentation Peer Group Under Act 345 Of P.A. Of 1990 On July 23, 1997

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Walter C. Dorman acting Chairman

For corners in

DELTA

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 41 N R 23 W
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

E-06 & E-07

28 July 1997

9:00 a.m.

Page 217

Walter C. Dorman Delta County, Mich. Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims E-06 W1/4 COR SEC 16 E-07 NW COR SEC 21

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 7.

I, M.P. DAVIS, in a field survey on 03 JUNE, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-06 [W1/4 COR SEC 16]- A.MERRYWEATHER, D.S.-1847-WOOD POST (MAPLE 10°-N30°E-25 LINKS)(BERCH 04°-S60°W-30 LINKS) M.S.McNABB-1933-ESTABLISHED AT 1/2 DISTANCE BETWEEN CORNERS-DROVE IRON-NO WIT'S NOTED

E-07 [NW COR SEC 21] A.MERRYWEATHER, D.S.-1847-WOOD POST (SUGAR 12°-S25°E-20 LINKS)(BASSWOOD 06°-N25°W-12 LINKS) M.S.McNABB-1933 IRON STAKE IN PLACE NBT'S FENCE POST S10°E 68' MAPLE STAKE S89°E 43.7'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-06 [W1/4 COR SEC 16] FOUND IN PLACE A 3/4" SOLID IRON PIN, COR IS 0.1' EAST & 2.89' SOUTH OF THE MIDPOINT BETWEEN SECTION CORNERS N & S. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER

E-07 [NW COR SEC 21] NO CORNER EVIDENCE FOUND-REPLACED CORNER POSITION FROM RETRACEMENT OF McNABB'S 1933 ROAD ALIGNMENT SURVEY OF COUNTY ROAD 519 BETWEEN THE NW COR OF SEC 33 & THE W1/4 COR OF SEC 16.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-06 SET OVER EXISTING MONUMENT A 5/8" X 18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION. SPRUCE 42" BALSAM 9" POWER POLE SURVEY MONUMENT SIGN POST N13°W 550'E S24°W N8°E 73.45' 59.16' 74.45' 9.20' (TO FACE)

E-07 SET A 5/8"X18" REBAR W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION & RAISED TO GRADE W/A MONUMENT BOX. 5/8" X 18" REBAR W/A 2" ALUM WIT'S CAP DRILL HOLE IN LARGE FIELD STONE SURVEY MONUMENT SIGN POST N35°W N35°E S49°E N86°W 78.45' 26.75' 43.93' 40.50' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. DAVIS Date 7/23/97

Surveyor's Michigan License No. 16926