

REMONUMENTATION

OCT 31 1997

COMMISSION

Approved By Delta County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On July 23, 1997

Robert R. Schuchling
Acting Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

DELTA

(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 41 N R 23 W
- 2. Property Controlling S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

F-11 & F-13

DATE 28 July 1997

9:00 P.M.

8 P. 219

Walter C. Thomas
Delta County, MI Reg. of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims F-11 N1/4 COR SEC 33 F-13 S1/4 COR SEC 33

I, M.P. DAVIS, in a field survey on 09 JUNE, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-13 [S1/4 COR SEC 33]- JOHN BURT D.S.-1845-WOOD POST (Y.BIRCH 30"-N68°W-49 LINKS)(Y.BIRCH 14"-N53°E-42 LINKS)
M.S.McNABB-1943-FOUND IN PLACE.NO DESCRIPTION OF MON FOUND. NOTED NEW BT'S-ELM 3"-SOUTH-39.1' & ELM 3"-S30°W-60.5'

F-11 [N1/4 COR SEC 33] A.MERRYWEATHER,D.S.-1847-WOOD POST (BURNT BIRCH 08"-N12°E-08 LINKS)(BURNT CEDAR 06"-S03°W-16 LINKS)
M.S.McNABB-1946-FOUND IN PLACE AT JCT OF FENCE LINES A SQ'D POST SCRIBED "1/4" NO WIT'S NOTED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 [S1/4 COR SEC 33] NO CORNER MONUMENT FOUND. RESTORED CORNER POSITION BY DISTANCE-DISTANCE INTERSECTION USING McNABB'S ELM BT (NOW A STUMP) SOUTH 39.1' & HIS W1/16 COR (CEDAR STAKE SCRIBED "1/8") WEST 1283.0 FEET. CORNER POSITION FALLS IN E-W FENCE LINE. ACCEPTED THIS POSITION AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.

F-11 [N1/4 COR SEC 33] FOUND IN PLACE AT JCT. OF ANCIENT FENCE LINES THE REMAINS OF SQ'D CEDAR POST WITH SCRIBE MARKS BARELY VISIBLE. DISTANCE WEST TO NW COR OF SEC 33 CHECKS VERY CLOSELY TO THE RECORDS OF McNABB. ACCEPTED EXISTING MONUMENT AS BEING THE BEST AVAILABLE EVIDENCE AS TO THE LOCATION OF THE POSITION OF THE ORIGINAL CORNER.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 SET A BERNTSEN A1NB30 ALUM MON W/A 3 1/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.
RED PINE 10" RED PINE 13" SPRUCE 5" SURVEY MONUMENT SIGN POST NOTE: FARM FIELDS IN THE
S57°E S36°W S38°E WEST NW & NE QUADRANTS
19.75' 16.73' 1.64' 2.57' (TO FACE)

F-11 SET A 4"X4"X36" CONC MON W/A 2 1/2" BRASS CAP STAMPED TO ID THE CORNER POSITION.
SURVEY MONUMENT SIGN POST NOTE: ALL FOUR QUADRANTS HAVE RECENTLY BEEN CLEAR CUT,
NORTH NO VIALBLE WIT'S ANYWHERE NEAR.
1.41' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 7/23/97

Surveyor's Michigan License No. 16926