

**SURVEY & REMONUMENTATION**

**JAN 14 1998**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

Approved By Delta County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 12/18, 1997  
*Robert B. Schmeling*  
 Acting Chairman

For corners in

DELTA  
 (County)

Located In:

Corner Code #

- |                                    |                             |                           |
|------------------------------------|-----------------------------|---------------------------|
| 1. Public Land Survey              | T <u>41</u> N R <u>23</u> W | <u>H-11</u> & <u>J-11</u> |
|                                    | T _____ R _____             | _____                     |
|                                    | T _____ R _____             | _____                     |
|                                    | T _____ R _____             | _____                     |
| 2. Property Controlling in Section | S _____ T _____ R _____     | _____                     |
|                                    | S _____ T _____ R _____     | _____                     |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____     | _____                     |
|                                    | S _____ T _____ R _____     | _____                     |

Recorded Dec 19 1997  
 at 9:00 am  
8 253  
*Robert B. Schmeling*  
 Acting Chairman

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims H-11 N1/4 COR SEC 34 J-11 N1/4 COR SEC 35

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, M.P. DAVIS, in a field survey on MAY, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-11 [N1/4 COR SEC 34]- A.MERRYWEATHER D.S.-1847-WOOD POST (BIRCH 09"-S20°W-23 LINKS)(BALSAM 06"-N35°W-27 LINKS)  
 JOHN S. CRAIG-COUNTY SURVYOR-1900-FOR TWP. ROAD-NO CORNER TO BE FOUND-SET STAKE 1/2 DISTANCE BETWEEN CORNERS-NO BT'S NOTED.  
 DELTA COUNTY ROAD COMMISSION-1947-FD IRON-BASSWOOD 14" N40°W 60.0' & MAPLE 12" N6°E 92.0'

J-11 [N1/4 COR SEC 35] A.MERRYWEATHER,D.S.-1847-WOOD POST (HEMLOCK 12"-S38°E-28 LINKS)(HEMLOCK 16"-WEST -09 LINKS)  
 JOHN S. CRAIG-COUNTY SURVEYOR-1900-FOR TWP. ROAD-STAKE IN PLACE (HEMLOCK 14"-S30°W-33 LINKS)(IRONWOOD 09"-N53°E-32.5 LINKS)  
 DELTA COUNTY ROAD COMMISSION-1947-FD IRON-NO WIT'S NOTED

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-11 [N1/4 COR SEC 35] FOUND IN PLACE A 1 1/4" IRON PIPE, NO EVIDENCE OF ROAD COMMISSION BT'S FOUND. DISTANCE WEST TO NW COR SEC 34 CHECKS WELL WITH ROAD COMMISSION RECORDS. ACCEPTED EXISTING MONUMENT AS BEING A CAREFUL & FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

J-11 [N1/4 COR SEC 35] FOUND IN PLACE & IN POOR CONDITION A 1/2" IRON PIN IN APPROXIMATE CENTER LINE OF THE E-W COUNTY RD. & IN LINE WITH AN ANCIENT FENCE LINE (DOWN & IN POOR CONDITION) TO THE NORTH. NO EVIDENCE OF CRAIG'S 1900 BT'S FOUND. PROPORTIONAL DISTANCE TO CORNERS 1/2 MILE E & W MATCHES WELL WITH RECORDS OF CRAIG.



**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-11 SET, OVER EXISTING MONUMENT, A 5/8" X 18" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.  

MAPLE 14"	MAPLE 12"	MAPLE 12"	POWER POLE	SURVEY MONUMENT SIGN POST
N67°W	N48°E	S51°W	S36°E	N85°W
44.13'	60.32'	68.83'	70.93'	

J-11 REPLACED EXISTING MONUMENT W/A 5/8" X 18" REBAR W/A 3/4" ALUM CAP STAMPED TO ID THE CORNER POSITION.  

MAPLE 08"	MAPLE 10"	MAPLE 05'	MAPLE 18"	SURVEY MONUMENT SIGN POST
N34°W	N13°E	S25°E	S24°W	N03°E
57.62'	46.90'	70.02'	70.85'	28.12' (TO FACE)

NOTE: BEARINGS TO REFERENCE OBJECTS ARE MAGNETIC & DISTANCES ARE TO A NAIL IN THE CENTER OF THE OBJECT, UNLESS OTHERWISE NOTED.

Signed by M.P. Davis Date 12/9/97  
 Surveyor's Michigan License No. 16926