

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>K-2</u>
2. PROPERTY CONTROLLING IN SECTION <u>1</u>	T. <u>41</u> N. S., R. <u>23</u> E. W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

DELTA Co.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on April 29 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

$\frac{1}{4}$ corner between Sec. 2/1	10 - S 1/16 corner on west section line.
Wood post	Not Previously established
Balsam 6 - S31°W - 10 links	
Do 9 - S45°E - 30 links	
Not previously established	

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

No old corner evidence found.	10 - M.P.O.L. between sec. cor. south and $\frac{1}{4}$ cor. north.
Set at the prop. distance to the G.L.O. Record and on line between the Sec. cors. $\frac{1}{2}$ mile north and $\frac{1}{2}$ mile south.	

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

8" B. ash N76°W - .644 chs. (42.5')	10 - 1" pipe, 4" aluminum cap
8" B. ash - S45°E - .211 chs. (13.9')	4" x 4" cedar post
16" cedar - S85°E - .056 chs. (3.7')	5" bl. ash - N38°W - 28.5'
1" pipe, 4" aluminum cap.	9" cedar - N38°E - 56.2'
	Falls in N.E. edge of the Days River.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____